

T - 12247

T-12247

NOAA FORM 76-35

U.S. DEPARTMENT OF COMMERCE
NATIONAL OCEANIC AND ATMOSPHERIC ADMINISTRATION
NATIONAL OCEAN SURVEY

DESCRIPTIVE REPORT

Type of Survey ... SHORELINE

Job No. PH-6211 Map No. T-12247

Classification No. Final Edition No. 1

Field Edited

LOCALITY

State ... WASHINGTON

General Locality ... HOOD CANAL

Locality ... Quilcene

1962 TO 1969

REGISTRY IN ARCHIVES

DATE

MAP NOT INSPECTED BY
QUALITY CONTROL OF PHOTOGRAMMETRY DIVISION
PRIOR TO REGISTRATION

NOAA FORM 76-36A (3-72) U. S. DEPARTMENT OF COMMERCE NATIONAL OCEANIC AND ATMOSPHERIC ADMIN. DESCRIPTIVE REPORT - DATA RECORD		TYPE OF SURVEY <input checked="" type="checkbox"/> ORIGINAL <input type="checkbox"/> RESURVEY <input type="checkbox"/> REVISED	SURVEY TP- T-122477 MAP EDITION NO. (1) MAP CLASS Field Edited JOB PH-6211
PHOTOGRAMMETRIC OFFICE Rockville Md.		LAST PRECEDING MAP EDITION	
OFFICER-IN-CHARGE V. Ralph Sobieralski		TYPE OF SURVEY <input type="checkbox"/> ORIGINAL <input type="checkbox"/> RESURVEY <input type="checkbox"/> REVISED	JOB PH- _____ MAP CLASS _____ SURVEY DATES: 19__ TO 19__
I. INSTRUCTIONS DATED			
1. OFFICE		2. FIELD	
Office original June 15, 1964 Amendment No. 1 Nov 22, 1965 " No. 2 Feb 16, 1966 " No. 3 July 1, 1966 " No. 4 April 5, 1967		Field Feb 5, 1963 Field Supplemental Feb 23, 1967	
II. DATUMS			
1. HORIZONTAL: <input checked="" type="checkbox"/> 1927 NORTH AMERICAN		OTHER (Specify)	
2. VERTICAL: <input checked="" type="checkbox"/> MEAN HIGH-WATER <input type="checkbox"/> MEAN LOW-WATER <input type="checkbox"/> MEAN LOWER LOW-WATER <input type="checkbox"/> MEAN SEA LEVEL		OTHER (Specify)	
3. MAP PROJECTION Polyconic Projection		4. GRID(S)	
5. SCALE 1:10,000		STATE WASHINGTON	ZONE North Zone
		STATE	ZONE
III. HISTORY OF OFFICE OPERATIONS			
OPERATIONS		NAME	DATE
1. AEROTRIANGULATION BY J. Gerlach Jan 1965 METHOD: LANDMARKS AND AIDS BY J. Perrow Jan 1965			
2. CONTROL AND BRIDGE POINTS PLOTTED BY J. C. Richter Jun 1967 METHOD: CHECKED BY H. Lucas Jun 1967			
3. STEREOSCOPIC INSTRUMENT PLANIMETRY BY J. C. Richter Jun 1967 COMPILATION CHECKED BY K. N. Maki Jun 1967 INSTRUMENT: Wild B-8 Stereoplotter SCALE: 1:30,000 CHECKED BY N.A.			
4. MANUSCRIPT DELINEATION PLANIMETRY BY J. C. Richter Jun 1967 CHECKED BY K. N. Maki Jun 1967 METHOD: Graphic B-8 Worksheets CHECKED BY N.A. SCALE: 1:10,000 HYDRO SUPPORT DATA BY J. C. Richter Jun 1967 CHECKED BY P. Dempsey Sep 1976			
5. OFFICE INSPECTION PRIOR TO FIELD EDIT BY K. N. Maki Jun 1967			
6. APPLICATION OF FIELD EDIT DATA BY J. Battley April 1969 CHECKED BY P. Dempsey April 1969			
7. COMPILATION SECTION REVIEW BY P. Dempsey Sep 1976			
8. FINAL REVIEW BY P. Dempsey Sep 1981			
9. DATA FORWARDED TO PHOTOGRAMMETRIC BRANCH BY			
10. DATA EXAMINED IN PHOTOGRAMMETRIC BRANCH BY			
11. MAP REGISTERED - COASTAL SURVEY SECTION BY H. D. Wolfe MAR 10 1965			

COMPILATION SOURCES

1. COMPILATION PHOTOGRAPHY

CAMERA(S) "W" & "L" Cameras 6" focal length		TYPES OF PHOTOGRAPHY LEGEND		TIME REFERENCE	
TIDE STAGE REFERENCE		(C) COLOR		ZONE	
<input checked="" type="checkbox"/> PREDICTED TIDES		(P) PANCHROMATIC		Pacific	
<input type="checkbox"/> REFERENCE STATION RECORDS		(I) INFRARED		MERIDIAN	
<input type="checkbox"/> TIDE CONTROLLED PHOTOGRAPHY				105th	
				<input type="checkbox"/> STANDARD	
				<input checked="" type="checkbox"/> DAYLIGHT	
NUMBER AND TYPE	DATE	TIME	SCALE	STAGE OF TIDE	
62 W 5412 thru 5414	7 Jun 1962	11:10	1:30,000	7.3 MLW	
65 L 5637 " 5639	15 Aug 1965	10:12	1:30,000 (Ratio)		

REMARKS

2. SOURCE OF MEAN HIGH-WATER LINE:
Office interpreted from computed tide values which determined the stage of tide at the time of photography listed in item 1.

3. SOURCE OF MEAN LOW-WATER OR MEAN LOWER LOW-WATER LINE:
No mean Lower Low water line delineated on this map.
See Final Review Report.

4. CONTEMPORARY HYDROGRAPHIC SURVEYS (List only those surveys that are sources for photogrammetric survey information.)

SURVEY NUMBER	DATE(S)	SURVEY COPY USED	SURVEY NUMBER	DATE(S)	SURVEY COPY USED

5. FINAL JUNCTIONS

NORTH	EAST	SOUTH	WEST
No contemporary Survey	T-12248	T-12252	T-12246

REMARKS

HISTORY OF FIELD OPERATIONS

I. FIELD INSPECTION OPERATION FIELD EDIT OPERATION.

OPERATION	NAME	DATE
1. CHIEF OF FIELD PARTY	R. B. Melby	May 1963
2. HORIZONTAL CONTROL	RECOVERED BY	R. B. Melby
	ESTABLISHED BY	
	PRE-MARKED OR IDENTIFIED BY	R. B. Melby
3. VERTICAL CONTROL	RECOVERED BY	N/A
	ESTABLISHED BY	N/A
	PRE-MARKED OR IDENTIFIED BY	N/A
4. LANDMARKS AND AIDS TO NAVIGATION	RECOVERED (<i>Triangulation Stations</i>) BY	N/A
	LOCATED (<i>Field Methods</i>) BY	N/A
	IDENTIFIED BY	N/A
5. GEOGRAPHIC NAMES INVESTIGATION	TYPE OF INVESTIGATION <input type="checkbox"/> COMPLETE BY <input type="checkbox"/> SPECIFIC NAMES ONLY BY <input checked="" type="checkbox"/> NO INVESTIGATION	
6. PHOTO INSPECTION	CLARIFICATION OF DETAILS BY	N/A
7. BOUNDARIES AND LIMITS	SURVEYED OR IDENTIFIED BY	N/A

II. SOURCE DATA

1. HORIZONTAL CONTROL IDENTIFIED	2. VERTICAL CONTROL IDENTIFIED		
Two stations			
PHOTO NUMBER	STATION NAME	PHOTO NUMBER	STATION DESIGNATION
62W5413	Grass 2, 1955		
62W5413	Sandy Shore, 1955		

3. PHOTO NUMBERS (*Clarification of details*)

4. LANDMARKS AND AIDS TO NAVIGATION IDENTIFIED
None

PHOTO NUMBER	OBJECT NAME	PHOTO NUMBER	OBJECT NAME

5. GEOGRAPHIC NAMES: REPORT NONE 6. BOUNDARY AND LIMITS: REPORT NONE

7. SUPPLEMENTAL MAPS AND PLANS
NONE

8. OTHER FIELD RECORDS (*Sketch books, etc. DO NOT list data submitted to the Geodesy Division*)
NONE

HISTORY OF FIELD OPERATIONS.

T-12247

I. FIELD INSPECTION OPERATION FIELD EDIT OPERATION.

OPERATION	NAME	DATE
1. CHIEF OF FIELD PARTY	R. E. Moses	April 1969
2. HORIZONTAL CONTROL	RECOVERED BY N/A ESTABLISHED BY N/A PRE-MARKED OR IDENTIFIED BY N/A	
3. VERTICAL CONTROL	RECOVERED BY N/A ESTABLISHED BY N/A PRE-MARKED OR IDENTIFIED BY N/A	
4. LANDMARKS AND AIDS TO NAVIGATION	RECOVERED (Triangulation Stations) BY N/A LOCATED (Field Methods) BY N/A IDENTIFIED BY N/A	
5. GEOGRAPHIC NAMES INVESTIGATION	TYPE OF INVESTIGATION <input type="checkbox"/> COMPLETE BY <input type="checkbox"/> SPECIFIC NAMES ONLY BY <input checked="" type="checkbox"/> NO INVESTIGATION	
6. PHOTO INSPECTION	CLARIFICATION OF DETAILS BY N/A	
7. BOUNDARIES AND LIMITS	SURVEYED OR IDENTIFIED BY N/A	

II. SOURCE DATA

1. HORIZONTAL CONTROL IDENTIFIED		2. VERTICAL CONTROL IDENTIFIED	
PHOTO NUMBER	STATION NAME	PHOTO NUMBER	STATION DESIGNATION

3. PHOTO NUMBERS (Clarification of details)

4. LANDMARKS AND AIDS TO NAVIGATION IDENTIFIED
None

PHOTO NUMBER	OBJECT NAME	PHOTO NUMBER	OBJECT NAME

5. GEOGRAPHIC NAMES: REPORT NONE

6. BOUNDARY AND LIMITS: REPORT NONE

7. SUPPLEMENTAL MAPS AND PLANS
NONE

8. OTHER FIELD RECORDS (Sketch books, etc. DO NOT list data submitted to the Geodesy Division)
NONE

RECORD OF SURVEY USE

T-12247

I. MANUSCRIPT COPIES

COMPILATION STAGES			DATE MANUSCRIPT FORWARDED	
DATA COMPILED	DATE	REMARKS	MARINE CHARTS	HYDRO SUPPORT
Shoreline, photo-hydro support points	June 1967			June 1967
Field edit applied	April 1969	Class I map		

II. LANDMARKS AND AIDS TO NAVIGATION

1. REPORTS TO MARINE CHART DIVISION, NAUTICAL DATA BRANCH

NUMBER	CHART LETTER NUMBER ASSIGNED	DATE FORWARDED	REMARKS

2. REPORT TO MARINE CHART DIVISION, COAST PILOT BRANCH. DATE FORWARDED: _____
 3. REPORT TO AERONAUTICAL CHART DIVISION, AERONAUTICAL DATA SECTION. DATE FORWARDED: _____


III. FEDERAL RECORDS CENTER DATA

1. BRIDGING PHOTOGRAPHS; DUPLICATE BRIDGING REPORT; COMPUTER READOUTS.
 2. CONTROL STATION IDENTIFICATION CARDS; FORM NOS 567 SUBMITTED BY FIELD PARTIES.
 3. SOURCE DATA (except for Geographic Names Report) AS LISTED IN SECTION II, NOAA FORM 76-36C. ACCOUNT FOR EXCEPTIONS:
 4. DATA TO FEDERAL RECORDS CENTER. DATE FORWARDED: 11/82

IV. SURVEY EDITIONS (This section shall be completed each time a new map edition is registered)

SECOND EDITION	SURVEY NUMBER TP - _____ (2)	JOB NUMBER PH - _____	TYPE OF SURVEY <input type="checkbox"/> REVISED <input type="checkbox"/> RESURVEY
	DATE OF PHOTOGRAPHY	DATE OF FIELD EDIT	MAP CLASS <input type="checkbox"/> II. <input type="checkbox"/> III. <input type="checkbox"/> IV. <input type="checkbox"/> V. <input type="checkbox"/> FINAL
THIRD EDITION	SURVEY NUMBER TP - _____ (3)	JOB NUMBER PH - _____	TYPE OF SURVEY <input type="checkbox"/> REVISED <input type="checkbox"/> RESURVEY
	DATE OF PHOTOGRAPHY	DATE OF FIELD EDIT	MAP CLASS <input type="checkbox"/> II. <input type="checkbox"/> III. <input type="checkbox"/> IV. <input type="checkbox"/> V. <input type="checkbox"/> FINAL
FOURTH EDITION	SURVEY NUMBER TP - _____ (4)	JOB NUMBER PH - _____	TYPE OF SURVEY <input type="checkbox"/> REVISED <input type="checkbox"/> RESURVEY
	DATE OF PHOTOGRAPHY	DATE OF FIELD EDIT	MAP CLASS <input type="checkbox"/> II. <input type="checkbox"/> III. <input type="checkbox"/> IV. <input type="checkbox"/> V. <input type="checkbox"/> FINAL

PH-6211
 SHORELINE MAPPING
 SCALE 1:10,000
 HOOD CANAL, WASH.



PHOTOGRAPHY
 • 1:30,000 Date Jun 62
 • 1:25,000 " Aug 65
 • 1:15,000 Jun 62

T-12247

SUMMARY TO ACCOMPANY
DESCRIPTIVE REPORT

This 1:10,000 scale shoreline manuscript is one of 17 maps that comprise Project Ph-6211, which covers an area in the Northern part of Hood Canal from Port Gamble Southward to Hood Point and includes all of Dabob Bay. All maps in this project were field edited and reviewed. The field edit was accomplished by the hydrographic field party for project OPR-412.

The initial purpose of this map was to provide support for our nautical and aeronautical charting program and provide photo-hydro support data for hydrography scheduled in the area.

A field investigation was performed prior to compilation in April to June 1963. This investigation was to establish control, in order to meet aerotriangulation requirements, and to locate all landmarks and aids previously undetermined. All fixed aids to navigation not previously located by triangulation were located by triangulation or traverse at this time.

Photo coverage for compilation and aerotriangulation was flown in June 1962 with the "W" Wild Aviogon camera at a scale of 1:30,000 with panchromatic film and in August 1965 with the "L" Wild camera at a scale of 1:30,000 (ratio to 1:10,000) with panchromatic film. The 1:10,000 scale ratio prints were used for field notes.

Analytical aerotriangulation was adequately provided by the Rockville office.

Compilation was performed at both the Rockville office and the Atlantic Marine Center. Five sheets (T-12248, T-12249, T-12250, T-12253 and T-12254) were compiled in the AMC office in July, August and September 1966. The other twelve sheets were compiled in the Rockville office in April, May and June 1967. The field edit was applied in the Rockville office only.

Final review for this map was performed in the Rockville office in 1981.

FIELD INSPECTION

There was no field inspection prior to compilation. Field work accomplished was limited to the recovery and identification of the horizontal control necessary for the aerotriangulation of the project.

See attached report on panelling of control.

Horizontal Control and Identification Report

Project Ph-6211

Hood Canal, Washington

April-June 1963

The following comments and remarks are pertinent to the conditions and methods utilized to perform the required photo-control in Project Ph-6211. (Reference control diagram Ph-6211, Hood Canal, Wash.)

Sheet T-12246

Station T.T. 1 RB (USGS), 1955 was identified by the substitute station method, incorporating a dog-leg traverse to one of the substitute stations.

Station LELAND, 1955 was not identified. See station LARSON, 1955 north of sheet T-12247.

Sheet T-12247

Station LARSON, 1955 was identified in lieu of station LELAND, 1955. Station SANDY SHORE, 1955 was identified by a traverse to the substitute stations. A sun azimuth was observed at both ends of the traverse to secure adequate azimuth control of the traverse of the traverse line. Station GRASS 2, 1955 was identified by the substitute station method.

Sheet T-12248 T-12249

Station HOOD CANAL LIGHT 4, 1961 was identified direct and by the reverse, substitute station method.

Sheet T-12249

Station SET 2, 1934 was identified by a single substitute station,

determined by a dog-leg traverse. Station HOOD CANAL LIGHT NO.1, 1945 was identified direct. The light is near SET 2, 1934 and can serve as a second identified point. Station WHITE, 1934 was identified by the substitute station methods, using a dog-leg traverse to determine one of the substitute stations.

During the location of station SISTERS ROCK LIGHT, 1963, observations involving station SHINE, 1927 failed to provide adequate azimuth checks.

Sheet T-12250

North of this sheet station HEAD, 1927 was identified by a single substitute station. Nearby station POINT HANNON LIGHT, 1945 was identified direct to afford another identified point. Station NORTH BASE, 1915 was identified by the substitute station method. Station PORT, 1927 was identified by the substitute station method.

Sheet T-12251

Station COMPUTER BLDG (USN), 1961 was identified by the substitute station method.

Sheet T-12252

Station HOOD CANAL LIGHT 10, 1963 was identified direct. A suitable substitute station could not be found, therefore station CURRANT 2 1934, about 1/3 mile to the southwest was identified with a single substitute station.

Sheet T-12253

No stations were identified in this sheet.

Sheet 12254

Station HOOD CANAL LIGHT NO. 1, 1945 was identified direct to augment identification of nearby station SET 2, 1934.

Sheet T-12255

Station SYLOPASH POINT LIGHT, 1963, was identified by the reverse substitute station method.

Sheet T-12256

Station PULALI 2, 1961 was identified direct. A suitable substitute could not be found.

Sheet T-12257

Station CURRANT 2, 1934 was identified with a single substitute station. This can serve as the second identification point in this area as HOOD CANAL LIGHT 10 1963 was identified direct. Station HAZEL POINT LIGHT, 1963 was identified direct. Nearby station OAK HEAD LIGHT, 1963 in sheet T-12261 was also identified direct to serve as the other required identified point. In the course of the location of station HAZEL POINT LIGHT, 1963, station HAZEL POINT 3, 1945 was found to be in error by about 36 feet. The azimuth of the line CHUTE 3, 1945-HAZEL POINT 3 1945 was in error by 10 minutes. A new position of HAZEL POINT 3, 1945 was determined by the field unit. Station TABOOK POINT LIGHT, 1963 was identified direct.

Sheet T-12258

Station BANGOR, 1955 was identified by a single substitute station. Nearby station BANGOR LOOKOUT TOWER, 1955 was identified direct.

Sheet T-12259

Station QUATSAP 2, 1934 was identified by the substitute station method utilizing a single closed triangle observation.

Sheet T-12260

Station BOULDER, 1878 was identified by two substitute stations.

Sheet T-12261

Station BOULDER, 1878

Station LONE ROCK, 1878 was identified by the substitute station method by a single closed triangle observation.

Sheet T-12314

No station were identified in the sheet.

None of the control identification was considered substandard.

Landmarks and aids

All landmarks and aids previously undetermined were located at this time. All fixed aids to navigation not previously located by triangulation were located by triangulation or traverse methods at this time.

Respectfully submitted

Robert B. Melby
Robert B. Melby
Surveying Technician

Aerotriangulation Report

Charge No. 21053

Hood Canal, Washington

21. Area Covered

The bridging covers the area of Hood Canal, approximately 20 miles northwest of Seattle, Washington.

22. Method

Six strips were bridged on the Zeiss C-8 stereoplanigraph to provide control for compilation of shoreline (see attached sketch). Strip 2 was not bridged because the area was duplicated by Strip 1. Strip 7 was adjusted on the IBM 650 and all other strips on the IBM 1620.

23. Adequacy of Control

Control positions were adequate for bridge adjustment. However, sub stations of Pulali 2, 1961 and Computer Building (USN) 1961 were impossible to locate with any accuracy due mainly to poor images. Sisters Rock Light, 1963 also had a very poor image on the photographs in strip 6.

No explanation could be found for the discrepancy of Tabook Point Light, 1963 and sub-station B of Hoods Point, 1878. Sub station B of Hoods Point was within accuracy limits on Strip 3.

All other points held within accuracy requirements.

24. Supplemental Data

Common tie points were hit between adjoining bridges and were averaged. Vertical control points were taken directly from the quads and can be expected to have only the accuracy of the contours of the quad itself.

25. Photography

Photography was adequate as to coverage. The overlap was too great on Strip 1, necessitating the use of every other photograph in the bridge. Definition was poor on the strips to the west, partially because of sun reflections.

Submitted by:

John T. Gerlach
John T. Gerlach


Approved by:

John D. Perrow, Jr.
John D. Perrow, Jr.

AEROTRIANGULATION SKETCH
 CHARGE No. 21053
 HOOD CANAL, WASHINGTON
 JAN, 1965

LEGEND

- △ CONTROL USED IN ADJUST.
- △ CONTROL USED AS CHECK



- 9) BOULDER, 1878
- 10) LONE ROCK 1878
- 11) OAK HEAD LT. 1963
- 12) HAZEL PT. LT. 1963
- 13) CURRANT 2, 1934
- 14) HOOD CANAL LT. 10, 1963
- 15) BANGOR LOOKOUT TWR. 1955
- 16) HOOD CANAL LT. 5
- 17) SET 2, 1934
- 18) HOOD CANAL LT. 4
- 19) SHINE 1927
- 20) WHITE 1924
- 21) HEAD 1927
- 22) ROCK ISLAND 1878
- 23) SISTERS ROCK LT. 1963
- 24) PORT 1927
- 25) PORT GAMBLE, MILL CHIM. 1934
- 26) PORT GAMBLE INNER LT. 1924
- 27) NORTH BASE, 1915
- 28) LAXSON 1955
- 29) SANDY SHORE 1955
- 30) POINT HANCOCK LT. 1945
- 31) BANGOR 1955

- 1) T.T.1 (USGS) 1955
- 2) GRASS 2, 65
- 3) COMPUTER BLDG. (USN) 1961
- 4) PULASKI 2, 1961
- 5) TABOOK Pt. LT. 1963
- 6) SYLOPASH Pt. LT. 1963
- 7) QUATSAP 2, 1934
- 8) HOODS POINT, 1878

DESCRIPTIVE REPORT CONTROL RECORD

MAP NO.	JOB NO.	GEODETTIC DATUM		ORIGINATING ACTIVITY		REMARKS
		PH-6211	NA. 1927	WASHINGTON	ROCKVILLE, MD.	
STATION NAME	SOURCE OF INFORMATION (Index)	AEROTRI-ANGULATION POINT NUMBER	COORDINATES IN FEET	GEOGRAPHIC POSITION		
			STATE	ϕ LATITUDE	λ LONGITUDE	
GRASS 2, 1955	Pg 1631	NA 1927	NAORTH	ϕ 47° 48' 47.494"		
			Y= 302,763.61	λ 122° 47' 38.677"		
LONGSPIT 2, 1955	Pg 1631	NA 1927	X=	ϕ 47° 50' 13.697"		
			Y=	λ 122° 48' 21.044"		
			X=	ϕ		
			Y=	λ		
			X=	ϕ		
			Y=	λ		
			X=	ϕ		
			Y=	λ		
			X=	ϕ		
			Y=	λ		
			X=	ϕ		
			Y=	λ		
			X=	ϕ		
			Y=	λ		
COMPUTED BY	J. PERROW	DATE	COMPUTATION CHECKED BY		DATE	
LISTED BY		JAN 1965	J. GERLACH		JAN 1965	
HAND PLOTTING BY	J. C. RICHTER	JUN 1967	HAND PLOTTING CHECKED BY		DATE	
			H. LOCAS		JUN 1967	

Compilation Report

T-12247

31. Delineation

The B-8 stereoplotter was used for delineation. The bridging photographs were not fully satisfactory due to poor definition. Rocks and features along the forshore were located graphically using 1:10,000 ratio photographs (Aug 15, 1965).

32. Control

See the Aerotriangulation Report for the adequacy of horizontal control. Vertical control was taken from USGS Quadrangle maps and used in the leveling of stereo models on the B-8.

33. Supplemental Data

None

34. Contours and Drainage

Contours - inapplicable

Drainage was compiled from interpretation of the photography.

35. Shoreline and alongshore detail

There was no field inspection. The MHWL was delineated by office interpretation from the photographs and computed tides. The shallow lines were office interpreted. Refer to notes to hydrographers.

36. Offshore detail

Photographs were of poor definition and offshore detail could not be clearly seen. Later "1965" photographs were used to locate offshore detail graphically.

37. Landmarks and Aids

None

38. Control for Future Surveys

None

39. Junctions

T-12248 to the East, in Agreement.

T-12252 to the South, in Agreement.

T-12246 to the West, in agreement.

No contemporary survey to the North.

40 thru 45

Inapplicable

46. Comparison with Existing Maps

Comparison has been made with USGS Quadrangle Quilcene, Washington scale 1:24,000, dated 1953.

47. Comparison with Nautical Charts

Comparison has been made with Nautical Chart 6422, scale 1:25,000, 3rd edition, Feb 8, 1965, corrected to June 11, 1966.

Items to be applied to Nautical Charts immediately. None.

Items to be carried forward. None.

Respectfully Submitted

John C. Richter
Carttographer

Approved and Forwarded:

K. Maki
Chief, Compilation Section

FIELD EDIT REPORT

HOOD CANAL AND DEBOB BAY, WASHINGTON

MARCH, APRIL 1969

PROJECT OPR - 412

This report covers the area in Hood Canal from Carson Point south to Quatsap Point and the entire Debob and Quilcene Bays.

The entire shore line was inspected using a small boat. The Field Edit copies (Discrepancy Prints) of the map manuscripts were used as a guide and all corrections, except as noted below, were recorded on them.

ADEQUACY OF COMPILATION:

The extent and accuracy of the maps appear to be reasonably complete, considering the compilation was accomplished without the benefit of Field Inspection.

METHODS:

The shoreline was inspected primarily with respect to the Discrepancy Prints of the map manuscript. All items specifically noted on the prints were investigated thoroughly. All shoreline was inspected and any comments were recorded on the Discrepancy Print. Where positions were needed, sextant cuts on Hydrographic Signals were recorded. These positions were numbered and plotted on the appropriate Boat Sheet of the area. The proper sheet is stated on the individual Discrepancy Prints.

Mean High Water was established with sextant angles and references to along shore objects and Hydrographic Signals. The shore is generally a sand gravel composition with areas cluttered with medium size boulders. The Dashed Line shown on the manuscripts were generally excellently positioned to indicate areas or limits of shoal water.

There are numerous homes and summer homes along the shore. Many have private railways or small mooring buoys offshore. The positions of the larger, most dangerous items have been noted.

SHEET T-12261:

Refer to Sheet DA-10-¹69.

Area is well settled. The major change in shoreline is the slide area on the upper right. The outline is as of the time noted.

SHEET T-12260:

Refer to Sheet DA-10-2-69.

Area is well settled. Shoreline of Misery Point is Rocky and rises sharply from the beach. The area is prone to slides.

SHEET T-12259:

Refer to Sheet DA-10-2-69.

The area at the mouth of the Duckabush River is extremely shallow and sandy. The high water line appears satisfactory, but is difficult to determine.

SHEET T-12257:

Refer to Sheet DA-10-1-69.

This area is generally uninhabited. Fisherman's Harbor is accessible only at or near high tide.

SHEET T-12258:

Refer to Sheet DA-10-1-69.

This area is well inhabited. The dashed shoreline is generally very steep with trees growing to the High Water Line.

SHEET T-12256:

Refer to Sheet DA-10-1-69.

SHEET T-12255:

Refer to Sheet DA-10-1-69.

The area is well inhabited. The Brinnon Flats area is very shallow. The High Water Line is as good as can be expected, considering the sand shoreline and the river mouth.

SHEET T-12252:

Refer to Sheet DA-10-3-69.

SHEET T-12251:

Refer to Sheet DA-10-3-69.

There are numerous buoys owned and maintained by the Navy off of the southern end of Bolton Peninsula. These are positioned on DA-10-3-69.

SHEET T-12246:

Refer to Sheet DA-10-3-69, Photo 62W5383, and Sketch Book.

The north end of Quilcene Bay is very shallow with miscellaneous piles, etc. Filings, bulkheads, etc. near East Quilcene have been Photo Identified on Photo 62W5383.

SHEET T-12314:

Refer to Sheet DA-10-1-69 and DA-10-2-69.

SHEET T-12247:

Refer to Sheet DA-10-3-69.


Tarboo Bay is dry, except for a shallow stream, and inaccessible at low water.

Respectfully Submitted,



Kanezo A. Domoto
LT, USESSA
Operations Officer
USC&GSS DAVIDSON

APPROVED & FORWARDED:



Roy E. Moses
CDR USESSA
Comdg. Officer
USC&GSS DAVIDSON

Review Report
T-12247
Shoreline
July 27, 1981

61. GENERAL STATEMENT

The discrepancy print for T-12247 is lost. The field edit report refers to Boat Sheet DA-10-3-69 for field edit application. A comparison was made with the hydrographic smooth sheet H-9038. Refer to item 64.

The dotted line outside the MHW line shows the limits of foreshore area visible on photography. There is no MLLW line on this map.

62. COMPARISON WITH REGISTERED TOPOGRAPHIC SURVEYS - Not applicable.

63. COMPARISON WITH MAPS OF OTHER AGENCIES - N/A.

64. COMPARISON WITH CONTEMPORARY HYDROGRAPHIC SURVEYS

A comparison was made with smooth sheet H-9038. There were what appeared to be logs compiled northeast of Long Spit on T-12247. No reference was made of these logs on the smooth sheet, therefore, they were removed from the manuscript. The hydrographic survey used some areas of the dotted foreshore line as their MLLW line.

65. COMPARISON WITH NAUTICAL CHARTS.

Comparison was made with chart 6422, scale 1:25,000, 3rd edition, Feb. 8, 1965, corrected to June 11, 1966. Except for minor shoreline differences to be expected with the passage of time, no significant changes were noted.

66. ADEQUACY OF RESULTS AND FUTURE SURVEYS

This map complies with project instructions and meets the requirements for Bureau Standards and National Standards of Map Accuracy.

Submitted by,



P. Dempsey
Final Reviewer

Approved and forwarded:

Chief, Photogrammetric Branch

Chief, Photogrammetry Division

GEOGRAPHIC NAMES

FINAL NAME SHEET

PH-6211 (Hood Canal, Wash.)

T-12247

Dabob

Dabob Bay

Long Spit

Tarboo Bay

Thorndyke ~~Thorndike~~ Creek - *J.P.*

Toandos Peninsula

Approved by:

A. J. Wraight

A. J. Wraight
Chief Geographer

Prepared by:

Frank W. Pickett

Frank W. Pickett
Cartographic Technician

Project PH-6211 Material on File

Hood Canal, Washington

Federal Records Center

Control Station Identification Cards
Field Edit Photographs
Computer Readouts
Field Edit Photographs
Field Edit Ozalids (Discrepancy Prints) for each map

Project Completion Report

Bureau Archives

Registered Copy of each map
Descriptive Report of each map

Reproduction Division

8x Reduction Negative of each map

Office of Staff Geographer

Geographer Names Standard

