


T-1323

3237



DESCRIPTIVE REPORT - DATA RECORD

TYPE OF SURVEY

- ☒ ORIGINAL
☐ RESURVEY
☐ REVISED

SURVEY TP. 13237

MAP EDITION NO. (1)

MAP CLASS III Final

JOB PH. 6303

PHOTOGRAMMETRIC OFFICE

Coastal Mapping Division
AMC Norfolk, VA

OFFICER-IN-CHARGE

Jeffrey G. Carlen

LAST PRECEDING MAP EDITION

TYPE OF SURVEY

- ☐ ORIGINAL
☐ RESURVEY
☐ REVISED

JOB PH. _____

MAP CLASS _____

SURVEY DATES:

19__ TO 19__

I. INSTRUCTIONS DATED

1. OFFICE

Aerotriangulation Jan 9, 1967
Compilation Mar 20, 1967
Compilation Supplement 1 Nov 6, 1970
Compilation Supplement 2 Nov 23, 1970
Compilation Supplement 3 Nov 5, 1971
Compilation Amendment 1 Dec 7, 1971

2. FIELD

Field Feb 10, 1966

II. DATUMS

1. HORIZONTAL:

☒ 1927 NORTH AMERICAN

OTHER (Specify)

2. VERTICAL:

- ☒ MEAN HIGH-WATER
☐ MEAN LOW-WATER
☒ MEAN LOWER LOW-WATER
☐ MEAN SEA LEVEL

OTHER (Specify)

3. MAP PROJECTION

polyconic

4. GRID(S)

STATE
AlaskaZONE
1

5. SCALE

1:10,000

STATE

ZONE

III. HISTORY OF OFFICE OPERATIONS

OPERATIONS		NAME	DATE
1. AEROTRIANGULATION	BY	J. Perrow	Dec 1970
METHOD: stereoplanigraph	LANDMARKS AND AIDS BY		
2. CONTROL AND BRIDGE POINTS	PLOTTED BY	J. Perrow	Dec 1970
METHOD: coradomat	CHECKED BY	H. Eichert	Dec 1970
3. STEREOSCOPIC INSTRUMENT	PLANIMETRY BY	R. White	Nov 1971
COMPILATION	CHECKED BY	A. Shands	Nov 1971
INSTRUMENT: Wild B-8	CONTOURS BY	N.A.	
SCALE: 1:10,000	CHECKED BY	N.A.	
4. MANUSCRIPT DELINEATION	PLANIMETRY BY	R. White	Nov 1971
	CHECKED BY	L. Graves	Nov 1971
METHOD: smooth drafted	CONTOURS BY	N.A.	
	CHECKED BY	N.A.	
SCALE: 1:10,000	HYDRO SUPPORT DATA BY	R. White	Nov 1971
	CHECKED BY	L. Graves	Nov 1971
5. OFFICE INSPECTION PRIOR TO FIELD EDIT	BY	L. Graves	Nov 1971
6. APPLICATION OF FIELD EDIT DATA	BY		
	CHECKED BY		
7. COMPILATION SECTION REVIEW	BY	L. Graves	Nov 1971
8. FINAL REVIEW	BY	L.O. Neterer, Jr.	Jan 1986
9. DATA FORWARDED TO PHOTOGRAMMETRIC BRANCH	BY	L.O. Neterer, Jr.	
10. DATA EXAMINED IN PHOTOGRAMMETRIC BRANCH	BY	P. Dempsey	June 1988
11. MAP REGISTERED - COASTAL SURVEY SECTION	BY	J. Nelson	July 1988

NOAA FORM 76-36B
(3-72)U. S. DEPARTMENT OF COMMERCE
NATIONAL OCEANIC AND ATMOSPHERIC ADMINISTRATION
NATIONAL OCEAN SURVEYT-13237
COMPILATION SOURCES

1. COMPILATION PHOTOGRAPHY

CAMERA(S) Wild RC-8"L"		TYPES OF PHOTOGRAPHY LEGEND (C) COLOR (P) PANCHROMATIC (I) INFRARED		TIME REFERENCE	
TIDE STAGE REFERENCE ☒ PREDICTED TIDES ☐ REFERENCE STATION RECORDS ☐ TIDE CONTROLLED PHOTOGRAPHY				ZONE Pacific MERIDIAN 120th	☒ STANDARD ☐ DAYLIGHT
NUMBER AND TYPE	DATE	TIME	SCALE	STAGE OF TIDE	
65L-5035-5036	Jul 30, 65	09:45	1:15,000	3.7 ft below MLLW	
65L-5111	Jul 30, 1965	10:41	1:30,000	2.2 bt below MLLW	

REMARKS

2. SOURCE OF MEAN HIGH-WATER LINE:

The mean high water line was compiled from the stereo models of the above listed 1:30,000 scale photography.

3. SOURCE OF MEAN LOW-WATER OR MEAN LOWER LOW-WATER LINE:

The mean lower low water line and/or ledge limits were compiled from the above listed photography.

4. CONTEMPORARY HYDROGRAPHIC SURVEYS (List only those surveys that are sources for photogrammetric survey information.)

SURVEY NUMBER	DATE(S)	SURVEY COPY USED	SURVEY NUMBER	DATE(S)	SURVEY COPY USED

5. FINAL JUNCTIONS

NORTH	EAST	SOUTH	WEST
CM-7207*	T-13238	T-11977	No survey

REMARKS

*Compilation did not extend to the northern limits of this map, no junction was made.

NOAA FORM 76-36C
(3-72)U. S. DEPARTMENT OF COMMERCE
NATIONAL OCEANIC AND ATMOSPHERIC ADMINISTRATION
NATIONAL OCEAN SURVEY

T-13237

HISTORY OF FIELD OPERATIONS

I. ☒ FIELD INSPECTION OPERATION☐ FIELD EDIT OPERATION

OPERATION	NAME	DATE
1. CHIEF OF FIELD PARTY	B. Williams	April 1966
2. HORIZONTAL CONTROL	RECOVERED BY ESTABLISHED BY PRE-MARKED OR IDENTIFIED BY	None None None
3. VERTICAL CONTROL	RECOVERED BY ESTABLISHED BY PRE-MARKED OR IDENTIFIED BY	N.A. N.A. N.A.
4. LANDMARKS AND AIDS TO NAVIGATION	RECOVERED (Triangulation Stations) BY LOCATED (Field Methods) BY IDENTIFIED BY	None None None
5. GEOGRAPHIC NAMES INVESTIGATION	TYPE OF INVESTIGATION ☐ COMPLETE ☐ SPECIFIC NAMES ONLY ☒ NO INVESTIGATION	
6. PHOTO INSPECTION	CLARIFICATION OF DETAILS BY	None
7. BOUNDARIES AND LIMITS	SURVEYED OR IDENTIFIED BY	N.A.

II. SOURCE DATA

1. HORIZONTAL CONTROL IDENTIFIED

None

2. VERTICAL CONTROL IDENTIFIED

N.A.

PHOTO NUMBER	STATION NAME	PHOTO NUMBER	STATION DESIGNATION

3. PHOTO NUMBERS (Clarification of details)

None

4. LANDMARKS AND AIDS TO NAVIGATION IDENTIFIED

None

PHOTO NUMBER	OBJECT NAME	PHOTO NUMBER	OBJECT NAME

5. GEOGRAPHIC NAMES: ☐ REPORT ☒ NONE6. BOUNDARY AND LIMITS: ☐ REPORT ☒ NONE

7. SUPPLEMENTAL MAPS AND PLANS

None

8. OTHER FIELD RECORDS (Sketch books, etc. DO NOT list data submitted to the Geodesy Division)

None

NOAA FORM 76-36D
(3-72)U. S. DEPARTMENT OF COMMERCE
NATIONAL OCEANIC AND ATMOSPHERIC ADMINISTRATIONT-13237
RECORD OF SURVEY USE

I. MANUSCRIPT COPIES

COMPILATION STAGES			DATE MANUSCRIPT FORWARDED	
DATA COMPILED	DATE	REMARKS	MARINE CHARTS	HYDRO SUPPORT
Compilation complete pending field edit	Nov 1971	Class III manuscript	Jan 5, 1972	Dec 21, 1971
Field edit applied compilation complete	Oct 6, 1976	Field edit postponed Class III manuscript	None	None
Final Review	Jan 1987	Final Class III map	June 1988	

II. LANDMARKS AND AIDS TO NAVIGATION None

1. REPORTS TO MARINE CHART DIVISION, NAUTICAL DATA BRANCH

NUMBER	CHART LETTER NUMBER ASSIGNED	DATE FORWARDED	REMARKS

2. ☐ REPORT TO MARINE CHART DIVISION, COAST PILOT BRANCH. DATE FORWARDED: None3. ☐ REPORT TO AERONAUTICAL CHART DIVISION, AERONAUTICAL DATA SECTION. DATE FORWARDED: _____

III. FEDERAL RECORDS CENTER DATA

1. ☒ BRIDGING PHOTOGRAPHS; ☒ DUPLICATE BRIDGING REPORT; ☒ COMPUTER READOUTS.
 2. ☐ CONTROL STATION IDENTIFICATION CARDS; ☐ FORM NOS 567 SUBMITTED BY FIELD PARTIES.
 3. ☐ SOURCE DATA (except for Geographic Names Report) AS LISTED IN SECTION II, NOAA FORM 76-36C.
 ACCOUNT FOR EXCEPTIONS:

4. ☐ DATA TO FEDERAL RECORDS CENTER. DATE FORWARDED: _____

IV. SURVEY EDITIONS (This section shall be completed each time a new map edition is registered)

SECOND EDITION	SURVEY NUMBER TP - _____ (2)	JOB NUMBER PH - _____	TYPE OF SURVEY ☐ REVISED ☐ RESURVEY MAP CLASS ☐ II. ☐ III. ☐ IV. ☐ V. ☐ FINAL
	DATE OF PHOTOGRAPHY	DATE OF FIELD EDIT	
THIRD EDITION	SURVEY NUMBER TP - _____ (3)	JOB NUMBER PH - _____	TYPE OF SURVEY ☐ REVISED ☐ RESURVEY MAP CLASS ☐ II. ☐ III. ☐ IV. ☐ V. ☐ FINAL
	DATE OF PHOTOGRAPHY	DATE OF FIELD EDIT	
FOURTH EDITION	SURVEY NUMBER TP - _____ (4)	JOB NUMBER PH - _____	TYPE OF SURVEY ☐ REVISED ☐ RESURVEY MAP CLASS ☐ II. ☐ III. ☐ IV. ☐ V. ☐ FINAL
	DATE OF PHOTOGRAPHY	DATE OF FIELD EDIT	

JOB PH-6303


CLARENCE STRAIT

ALASKA

SHORELINE MAPPING

Scales 1:5,000 & 1:10,000

REVISED 9/23/76 RWW
 REVISED 10/7/86 D.B.
 T-13240 CANCELED
 REVISED 12/11/86 JDM
 T-13381 CANCELED (1976)



SUMMARY TO ACCOMPANY
DESCRIPTIVE REPORT

T-13237

This 1:10,000 scale shoreline map is one of thirty-four maps that comprise project PH-6303, Clarence Strait, Alaska. This project encompasses Clarence Strait and Ernest Sound, latitude $55^{\circ} 28' 45''$ north to latitude $56^{\circ} 00' 00''$ and longitude $131^{\circ} 55' 00''$ west to longitude $132^{\circ} 45' 00''$.

Photographic coverage was provided in July 1965 using black and white panchromatic film with the "L" camera (focal length 152.21 millimeters) at 1:15,000 and 1:30,000 scale.

Field work prior to compilation consisted of the photoidentification of horizontal control for bridging in May 1966.

Analytic aerotriangulation was performed at the Washington Science Center in December 1970.

Only about sixty percent of this map could be compiled due to insufficient photo coverage. This compilation was done at the Atlantic Marine Center during November 1971.

No field edit was accomplished in the area of this map. It was cancelled in October 1976. It will be registered as a Final Class III map.

Final review was completed at the Atlantic Marine Center during January 1987.

This Descriptive Report contains all pertinent information used to compile this Final map.

The original base map and all pertinent data were forwarded to the Washington Science Center for final registration.

FIELD INSPECTION

There was no photo field inspection prior to compilation. Field work accomplished was limited to the recovery and identification of the horizontal control necessary for the aerotriangulation of the project.

Photogrammetric Plot Report
Job PH-6303
Clarence Strait, Alaska
Part II - Northern Half

December 3, 1970

21. Area Covered

The area covered is in and around the junction of Ernest Sound and Clarence Strait, Alaska. Included are T-Sheets 11977 thru 11982, 12363 thru 12371, 12374, and 13237 thru 13240, at 1:10,000 scale, in Zone 1, Alaska Plane Coordinates.

22. Method

Seven strips were bridged on the stereoplanigraph and adjusted by I.B.M. 1620 methods. Strip #4 (63-W-7254 thru 7258) was adjusted on three triangulation sub-stations and two tie points from Strip #3 (Part I). Companion sub-stations and additional tie points served as checks. Strip #7 (65-L-5098 thru 5105) was adjusted on four triangulation sub-stations with companion sub-stations and tie points from Strip #12 as checks. Strip #8 (63-W-7324 thru 7330) was bridged only in part. 63-W-7324 thru 7328 was bridged and adjusted by a first order curve (straight line). The method employed two sub-stations for adjustment, with companion sub-stations and six tie points as checks. The remainder of the Strip (63-W-7329 and 7330) must be detailed graphically from ratio prints. Strip #9 (65-L-5109 thru 5116) was adjusted on four triangulation sub-stations with companion sub-stations, one additional triangulation station and five tie points with Strip #10 as checks. Strip #10 (63-W-7311 thru 7319) was bridged on three triangulation sub-stations with companion sub-stations and eleven tie points with Strips #8 and #9 as checks. Strip #11 (63-W-7291 thru 7306) was adjusted on four triangulation sub-stations and checked with tie points from Strip #6. Strip #12 (65-L-5091 thru 5096) was adjusted on four triangulation sub-stations with tie points from Strips #4 and #7 as checks. All points were drilled on the PUG. All tie points between strips were averaged. Some outlying islands in Sheet T-11977 and T-11978 could not be covered by bridging, nor can the area be compiled, with any accuracy, by graphic methods. Completion of these two sheets should be completed by the ship during the hydrographic survey.

23. Adequacy of Control

Horizontal control was adequate and complied with project instructions. All stations held within National Map Accuracy Standards with the following exceptions:

- (1) Drag, 1916 SS "C". This position was of poor image quality. In addition, it was allowed to drift by using tie points from Strip #3, as control on Strip #4. This solution provided the best overall fit.


24. Supplemental Data

Local GS quads were used to provide level points for bridging Operations. Due to the nature of the terrain and the scale of the quads, these elevations are very approximate.

25. Photography

Photography was good in coverage, overlap, and definition.

Submitted by:


John D. Perrow, Jr.

Approved by:


Henry P. Eichert
Chief, Aerotriangulation Section

Notes to Compiler
PH-6303
Clarence Strait, Alaska

December 3, 1970

Strip #4 does not fit within itself too well. However, the best overall fit was made so that the strip could be tied to Strip #3 (Part I), which had been compiled at an earlier date.

Strip #8 is positioned too far out over the water to provide more than a quarter of a model in that portion of the strip north of triangulation station Mabel. These small portion models would be extremely difficult to bridge, and equally as difficult to set in a compilation instrument. Therefore, points common to both strips in that area were selected in critical areas to establish ratioing constants for Strip #8, so that those photographs could be used in compiling the alongshore detail by graphic methods.

Just south of the area covered by Strip #9, are a number of islands which could not be covered by bridging operations, due to excessive water areas. These islands are located on T-Sheets 11977 and 11978. Ratio prints of this area were made at a three time enlargement, however, these are uncontrolled, and the exact scale cannot be determined. It is recommended that the islands on these two T-Sheets be located and positioned by the hydrographic survey party.

Strip #11. It is recommended that the area covered by model 63-W-7291 - 7292 be detailed from Strip #6 (Part I), since Strip #6 seems to be the stranger photogrammetric bridge.

Note: The published position of station HASH, 1966, is in error. A new position was provided by Geodesy. The sub-stations for Station OVAL, 1916, could not be seen on the bridging photography.

*No photo coverage on the northern tip of T-13234 as seen at T-13240.
Points on T-13234 and 13240 must be plotted by hand as no photo coverage.*

PROJECT PH-6303

SHORELINE MAPPING

NOV. 1970

ALASKA

PART II

CLARENCE STRAIT

SCALE ^{TAB} 1:10,000

63-W-7306

56

56°00'00"

56°00'30"

63-W-7311

132°15'00"

132°10'00"

132°06'00"

132°05'00"

132°00'00"

131°55'00"

3304

76

211

141

219

21

35

23

57470

COMPILATION REPORT
T-13237

31. DELINEATION

Compilation was done using the Wild B-8 and 1:30,000 scale photography. There was no Field Inspection prior to compilation.

Due to insufficient coverage of the area by the bridging photography, no compilation could be done north of Latitude 55° 58' 30".

32. CONTROL

See Photogrammetric Plot Report PH-6303, Part II, Northern Half dated December 3, 1970.

33. SUPPLEMENTAL DATA

None

34. CONTOURS AND DRAINAGE

Contours are inapplicable. Drainage was compiled from office interpretation of the photographs.

35. SHORELINE AND ALONGSHORE DETAILS

All details were compiled from office interpretation of the photographs.

36. OFFSHORE DETAIL

None

37. LANDMARKS AND AIDS

None

T-13237

38. CONTROL FOR FUTURE SURVEYS

None

39. JUNCTIONS

See Form 76-36d item 5 included with this report.

40. HORIZONTAL AND VERTICAL ACCURACY

No Statement

46. COMPARISON WITH EXISTING MAPS

A comparison has been made with U.S.G.S. Quad CRAIG (D-1) ALASKA scale 1:63,360, dated 1951.

47. COMPARISON WITH NAUTICAL CHARTS

A comparison has been made with U.S.C. & G.S. Chart 8161, scale 1:80,000 dated 3rd edition April 11, 1966.

ITEMS TO BE APPLIED TO NAUTICAL CHARTS IMMEDIATELY

None

ITEMS TO BE CARRIED FORWARD

None

Approved and Forwarded

Respectfully submitted

Richard R. White
Richard R. White
Cartographic Technician
November 5, 1971

Approved

A. C. Rauck, Jr.
A. C. Rauck, Jr.
Chief, Coastal Mapping Section

OCT 23 1986

GEOGRAPHIC NAMES

FINAL NAME SHEET

PH-6303 (Clarence Strait, Alaska)


T-13237

Brownson Island

Canoe Passage

Etolin Island

Approved:



Charles E. Harrington
Chief Geographer
Nautical Charting Division
Charting and Geodetic Services

REVIEW REPORT T-13237
SHORELINE

61. GENERAL STATEMENT

See Summary included with this Report. Insufficient photo coverage prevented the completion of this map. No field edit was accomplished north of latitude $55^{\circ} 58' 30''$ so this map is to be registered as a Final Class III map.

62. COMPARISON WITH REGISTERED TOPOGRAPHIC SURVEYS:

Not applicable.

63. COMPARISON WITH MAPS OF OTHER AGENCIES

A comparison was made with U. S. Geological Survey Quadrangle Craig (D-1), Alaska, scale 1:63,360 dated 1951.

64. COMPARISON WITH CONTEMPORARY HYDROGRAPHIC SURVEYS


There is no contemporary hydrographic survey within the limits of this map.

65. COMPARISON WITH NAUTICAL CHARTS:

A comparison was made with the following NOS charts: 17385, 11th edition, dated August 11, 1984, scale 1:80,000; 17360, 26th edition, dated August 18, 1984, scale 1:217,828; and 17420, 23rd edition, dated March 16, 1985, scale 1:229,376.

66. ADEQUACY OF RESULTS AND FUTURE SURVEYS

This map complies with the Project Instructions and meets the requirements for National Standards of Map Accuracy.



RECORD OF APPLICATION TO CHARTS

FILE WITH DESCRIPTIVE REPORT OF SURVEY NO.

INSTRUCTIONS

A basic hydrographic or topographic survey supersedes all information of like nature on the uncorrected chart.

1. Letter all information.
2. In "Remarks" column cross out words that do not apply.
3. Give reasons for deviations, if any, from recommendations made under "Comparison with Charts" in the Review.

[illegible]