

TP 00270

TP 00270

NOAA FORM 76-35

U.S. DEPARTMENT OF COMMERCE
NATIONAL OCEANIC AND ATMOSPHERIC ADMINISTRATION
NATIONAL OCEAN SURVEY

DESCRIPTIVE REPORT

Type of Survey Shoreline
Job No. PH-7101 Map No. TP-00270
Classification No. Edition No. 1
Field Edited Map

LOCALITY

State South Carolina and Georgia
General Locality Charleston to Savannah
Locality EDISTO ISLAND

1970 TO 1974

REGISTRY IN ARCHIVES

DATE

MAP NOT INSPECTED IN QUALITY CONTROL PRIOR
TO REGISTRATION

NOAA FORM 76-36A (3-72)		U. S. DEPARTMENT OF COMMERCE NATIONAL OCEANIC AND ATMOSPHERIC ADMIN.		TYPE OF SURVEY		SURVEY TP. 00270	
DESCRIPTIVE REPORT - DATA RECORD				☒ ORIGINAL		MAP EDITION NO. (1)	
				☐ RESURVEY		MAP CLASS FINAL(F.E.)	
				☐ REVISED		JOB PH. 7101	
PHOTOGRAMMETRIC OFFICE				LAST PRECEDING MAP EDITION			
Coastal Mapping Division (Norfolk)				TYPE OF SURVEY		JOB PH. _____	
OFFICER-IN-CHARGE				☐ ORIGINAL		MAP CLASS _____	
Jeffrey G. Carlen, Cdr.				☐ RESURVEY		SURVEY DATES:	
				☐ REVISED		19__ TO 19__	
I. INSTRUCTIONS DATED							
1. OFFICE				2. FIELD			
Aerotriangulation May, 1972				Sept. 17, 1970			
Compilation Sept, 1973							
II. DATUMS							
1. HORIZONTAL: ☒ 1927 NORTH AMERICAN				OTHER (Specify)			
2. VERTICAL: ☒ MEAN HIGH-WATER ☐ MEAN LOW-WATER ☐ MEAN LOWER LOW-WATER ☐ MEAN SEA LEVEL				OTHER (Specify)			
3. MAP PROJECTION							

NOAA FORM 76-36B
(3-72)

TP-00270

U. S. DEPARTMENT OF COMMERCE
NATIONAL OCEANIC AND ATMOSPHERIC ADMINISTRATION
NATIONAL OCEAN SURVEY

COMPILATION SOURCES

1. COMPILATION PHOTOGRAPHY

CAMERA(S) Wild RC-8 "E" and "L"		TYPES OF PHOTOGRAPHY LEGEND		TIME REFERENCE	
TIDE STAGE REFERENCE SAVANNAH RIVER ENT.		(C) COLOR X (P) PANCHROMATIC (I) INFRARED X		ZONE Eastern	☒ STANDARD
☒ PREDICTED TIDES (Hilton Head) ☐ REFERENCE STATION RECORDS ☒ TIDE CONTROLLED PHOTOGRAPHY				MERIDIAN 75th	☐ DAYLIGHT
NUMBER AND TYPE	DATE	TIME	SCALE	STAGE OF TIDE	
*71 E(I) 2382	3/30/71	09:43	1:30,000	± 0.2 ft. at MHW	
70 L(C) 9830	11/4/70	11:55	1:40,000	7.1 ft. above MLW	
*71 E(C) 2302	3/28/71	15:32	1:30,000	± 0.2 ft. at MLW	

REMARKS

*Tide coordinated infrared photography.

2. SOURCE OF MEAN HIGH-WATER LINE:

Tide coordinated infrared photography.

3. SOURCE OF MEAN LOW-WATER OR MEAN LOWER LOW-WATER LINE:

Tide coordinated infrared photography

4. CONTEMPORARY HYDROGRAPHIC SURVEYS (List only those surveys that are sources for photogrammetric survey information.)

SURVEY NUMBER	DATE(S)	SURVEY COPY USED	SURVEY NUMBER	DATE(S)	SURVEY COPY USED

5. FINAL JUNCTIONS

NORTH	EAST	SOUTH	WEST
TP-00267	No Survey	No Survey	TP-00269

REMARKS

TP-00270

HISTORY OF FIELD OPERATIONS

I. ☒ FIELD INSPECTION OPERATION☐ FIELD EDIT OPERATION

OPERATION	NAME	DATE
1. CHIEF OF FIELD PARTY	Joseph K. Wilson	1971
2. HORIZONTAL CONTROL	RECOVERED BY R.E. Kesselring	1971
	ESTABLISHED BY NA	
	PRE-MARKED OR IDENTIFIED BY R.E. Kesselring	1971
3. VERTICAL CONTROL	RECOVERED BY NA	
	ESTABLISHED BY NA	
	PRE-MARKED OR IDENTIFIED BY NA	
4. LANDMARKS AND AIDS TO NAVIGATION	RECOVERED (Triangulation Stations) BY None	
	LOCATED (Field Methods) BY None	
	IDENTIFIED BY None	
5. GEOGRAPHIC NAMES INVESTIGATION	TYPE OF INVESTIGATION ☐ COMPLETE ☐ SPECIFIC NAMES ONLY BY ☒ NO INVESTIGATION	
6. PHOTO INSPECTION	CLARIFICATION OF DETAILS BY None	
7. BOUNDARIES AND LIMITS	SURVEYED OR IDENTIFIED BY NA	

II. SOURCE DATA

1. HORIZONTAL CONTROL IDENTIFIED None		2. VERTICAL CONTROL IDENTIFIED NA	
PHOTO NUMBER	STATION NAME	PHOTO NUMBER	STATION DESIGNATION
3. PHOTO NUMBERS (Clarification of details) None			
4. LANDMARKS AND AIDS TO NAVIGATION IDENTIFIED None			
PHOTO NUMBER	OBJECT NAME	PHOTO NUMBER	OBJECT NAME
5. GEOGRAPHIC NAMES: ☐ REPORT ☒ NONE		6. BOUNDARY AND LIMITS: ☐ REPORT ☒ NONE	
7. SUPPLEMENTAL MAPS AND PLANS			
8. OTHER FIELD RECORDS (Sketch books, etc. DO NOT list data submitted to the Geodesy Division)			

TP-00270

HISTORY OF FIELD OPERATIONS

I. ☐ FIELD INSPECTION OPERATION☒ FIELD EDIT OPERATION

OPERATION	NAME	DATE
1. CHIEF OF FIELD PARTY	R.D. Black	Feb. 1974
2. HORIZONTAL CONTROL	R.D. Black	Feb. 1974
RECOVERED BY	NA	
ESTABLISHED BY	R.D. Black	Feb. 1974
PRE-MARKED OR IDENTIFIED BY	NA	
3. VERTICAL CONTROL	NA	
RECOVERED BY	NA	
ESTABLISHED BY	NA	
PRE-MARKED OR IDENTIFIED BY	NA	
4. LANDMARKS AND AIDS TO NAVIGATION	R.D. Black	Feb. 1974
RECOVERED (Triangulation Stations) BY	R.D. Black	Feb. 1974
LOCATED (Field Methods) BY	R.D. Black	Feb. 1974
IDENTIFIED BY		
5. GEOGRAPHIC NAMES INVESTIGATION		
TYPE OF INVESTIGATION		
☐ COMPLETE		
☐ SPECIFIC NAMES ONLY		
☒ NO INVESTIGATION		
6. PHOTO INSPECTION	R.D. Black	Feb. 1974
CLARIFICATION OF DETAILS BY	NA	
7. BOUNDARIES AND LIMITS	NA	
SURVEYED OR IDENTIFIED BY		

II. SOURCE DATA

1. HORIZONTAL CONTROL IDENTIFIED

2. VERTICAL CONTROL IDENTIFIED

PHOTO NUMBER	STATION NAME	PHOTO NUMBER	STATION DESIGNATION
28 MAR 71E-2302	EDISTO BEACH WATER CO. TANK, 1967		

3. PHOTO NUMBERS (Clarification of details)

28MAR71E-2302

4. LANDMARKS AND AIDS TO NAVIGATION IDENTIFIED

PHOTO NUMBER	OBJECT NAME	PHOTO NUMBER	OBJECT NAME
28 MAR 71E-2302	EDISTO BEACH WATER CO. TANK, 1967		
28 MAR 71E-2302	MICROWAVE RELAY TOWER (See back of photo)		

5. GEOGRAPHIC NAMES: ☐ REPORT ☒ NONE6. BOUNDARY AND LIMITS: ☐ REPORT ☒ NONE

7. SUPPLEMENTAL MAPS AND PLANS

Two (2) CSI forms for Photo Points 70-01 and 70-02

8. OTHER FIELD RECORDS (Sketch books, etc. DO NOT list data submitted to the Geodesy Division)

Two (2) Form 76-40; one originating in field and one originating in photogrammetric office.

One (1) copy Form 526 (Recovery Note)

NOAA FORM 76-36D
(3-72)U. S. DEPARTMENT OF COMMERCE
NATIONAL OCEANIC AND ATMOSPHERIC ADMINISTRATIONTP-00270
RECORD OF SURVEY USE

I. MANUSCRIPT COPIES

COMPILATION STAGES			DATE MANUSCRIPT FORWARDED	
DATA COMPILED	DATE	REMARKS	MARINE CHARTS	HYDRO SUPPORT
Manuscript complete pending field edit	11/ /73	Class III Manuscript Superseded	2/4/74	12/13/73 Field Edit:
Field edit applied Compilation complete	3/ /74	Class I Superseded	9/10/74	
Final Review	10/ /75		1/30/76	

II. LANDMARKS AND AIDS TO NAVIGATION

1. REPORTS TO MARINE CHART DIVISION, NAUTICAL DATA BRANCH

NUMBER	CHART LETTER NUMBER ASSIGNED	DATE FORWARDED	REMARKS
1	59174	5/22/74	Landmarks for Charts

2. ☒ REPORT TO MARINE CHART DIVISION, COAST PILOT BRANCH. DATE FORWARDED: 5/22/743. ☒ REPORT TO AERONAUTICAL CHART DIVISION, AERONAUTICAL DATA SECTION. DATE FORWARDED: 5/22/74

III. FEDERAL RECORDS CENTER DATA

1. ☒ BRIDGING PHOTOGRAPHS; ☒ DUPLICATE BRIDGING REPORT; ☒ COMPUTER READOUTS.
 2. ☐ CONTROL STATION IDENTIFICATION CARDS; ☒ FORM NOS 76-40 567 SUBMITTED BY FIELD PARTIES.
 3. ☒ SOURCE DATA (except for Geographic Names Report) AS LISTED IN SECTION II, NOAA FORM 76-36C.
 ACCOUNT FOR EXCEPTIONS:

4. ☐ DATA TO FEDERAL RECORDS CENTER, DATE FORWARDED: _____

IV. SURVEY EDITIONS (This section shall be completed each time a new map edition is registered)

SECOND EDITION	SURVEY NUMBER TP - _____ (2)	JOB NUMBER PH - _____	TYPE OF SURVEY ☐ REVISED ☐ RESURVEY MAP CLASS ☐ II. ☐ III. ☐ IV. ☐ V. ☐ FINAL
	DATE OF PHOTOGRAPHY	DATE OF FIELD EDIT	
THIRD EDITION	SURVEY NUMBER TP - _____ (3)	JOB NUMBER PH - _____	TYPE OF SURVEY ☐ REVISED ☐ RESURVEY MAP CLASS ☐ II. ☐ III. ☐ IV. ☐ V. ☐ FINAL
	DATE OF PHOTOGRAPHY	DATE OF FIELD EDIT	
FOURTH EDITION	SURVEY NUMBER TP - _____ (4)	JOB NUMBER PH - _____	TYPE OF SURVEY ☐ REVISED ☐ RESURVEY MAP CLASS ☐ II. ☐ III. ☐ IV. ☐ V. ☐ FINAL
	DATE OF PHOTOGRAPHY	DATE OF FIELD EDIT	

SCALE 1:10,000 & 1:20,000

Official Mileage
for Cost Accounts

Sheet No. --Area Co. III.

TP-00257	8
TP-00258	7
TP-00259	9
TP-00270	1
TP-00271	10
TP-00272	4
TP-00273	1
TP-00274	3
TP-00275	3
TP-00276	3
TP-00277	12
TP-00278	4
TP-00279	3

Total 68

000

30'

84.08
55.08
55.08

188

SUMMARY TO ACCOMPANY
DESCRIPTIVE REPORT TP-00270

This 1:20,000 scale shoreline manuscript is one of nine 1:20,000 scale and four 1:10,000 scale maps which comprise Project PH-7101, Charleston, SC to Savannah, GA. This is one of several projects that make up the Southern Coastal Plains Expedition, SCOPE. It is not a standard shoreline survey because compilation was limited to the shoreline and only a limited amount of interior detail. Shoreline of bays, inlets, canals or rivers that may be within the geographic limits of this map were not delineated. This deviation from written instructions was brought about by verbal instructions telephoned from the Rockville Office to the Chief, Coastal Mapping Section, AMC.

Field work prior to compilation consisted of premarking horizontal control for bridging.

Analytic aerotriangulation was done in the Rockville Office in 1973 using the color bridging photography dated November 1970. Bridge points were dropped common to the 1:30,000 scale March 1971 infrared photography for ordering ratios.

Compilation was done at the Atlantic Marine Center in October and November 1973. Using the 1:40,000 scale color bridging photography, the Wild B-8 was used to compile inshore features and to drop shoreline pass points common to the March 1971 tide-coordinated infrared photography. The mean high and mean low water lines were then delineated graphically from these tide-coordinated photographs.

Field edit was done in February 1974.

Final review was done at the Atlantic Marine Center in October, 1975.

The original manuscript is a stabilene sheet 10 minutes in latitude by 10 minutes in longitude.

A stable base copy and a negative of the final reviewed manuscript were forwarded for record and registry.

Photogrammetric Plot Report
Charleston to Savannah
South Carolina and Georgia
Job PH - 710I

21. Area Covered

This report covers nine 1:20,000 sheets, TP-00267, TP-00268, TP-00269, TP-00270, TP-00271, TP-00272, TP-00273, TP-00277, TP-00279 and four 1:10,000 sheets, TP-00274, TP-00275, TP-00276, and TP-00278 from Kiawah River, South Carolina, to Tybee Island, Georgia.

22. Method

Eight strips 1:40,000 scale color photography were bridged by analytic aerotriangulation methods and adjusted to ground on South Carolina South State Plane coordinate system. Bridge points were used on 1:30,000 scale infrared photography for ratioing photographs to be used in compiling the Mean Low- and Mean High-Water Line. Ratio prints of infrared photography covering Mean Low- and Mean High-Water were ordered. (One each of cronapaque). Tie points were used to augment datum between strips. Data for plotting manuscripts for compilation were assembled for ruling and plotting by the Coradomat and Calcomp.

23. Adequacy of Control

The horizontal control provided was adequate except for Fusky (USE) 1932 sub stations A and C, which held in strip one and did not hold in strip two, because of poor image points. Also, Chan, 1933, substation A and C did not hold in strip four because of poor image points.

All other control held within the accuracy required by National Standards of Map Accuracy at 1:20,000 and 1:10,000 scale.

24. Supplemental Data

U.S. Geological Survey quadrangles were used to provide elevations for vertical adjustments of bridges.

25. Photography

RC-8 color film positives were adequate as to coverage, overlay, and definition.

Submitted by,

Robert B. Kelly

Robert B. Kelly
12-10-73

Approved and forwarded:

J. D. Perrow, Jr.

J. D. Perrow, Jr.

Chief, Aerotriangulation Section

PH-7101
Charleston to Savannah


NOTE TO COMPILER

Foreshore Cross Section points listed below were omitted during bridging. Points should be dropped during compilation.

Section II	68-01
Section VII	69-01
Section VIII	69-02
Section IX	73-01
Section XIII	79-01

CHARLESTON to SAVANNAH
SO. CAROLINA to GEORGIA
SHORELINE MAPPING

SCALE 1:10,000 & 1:20,000



DESCRIPTIVE REPORT CONTROL RECORD

MAP NO. TP-00270	JOB NO. PH-7101	SOURCE OF INFORMATION (Index)	AEROTRI- ANGULATION POINT NUMBER	GEODETTIC DATUM N.A. 1927		ORIGINATING ACTIVITY	
				COORDINATES IN FEET STATE South ZONE Carolina South	GEOGRAPHIC POSITION ϕ LATITUDE λ LONGITUDE	REMARKS	
EDISTO BEACH WATER CO., TANK, 1963		Vol. III Pg. 390		X=	ϕ 32° 29' 02.042"		
				Y=	λ 80° 19' 55.696"		
				X=	ϕ		
				Y=	λ		
				X=	ϕ		
				Y=	λ		
				X=	ϕ		
				Y=	λ		
				X=	ϕ		
				Y=	λ		
				X=	ϕ		
				Y=	λ		
				X=	ϕ		
				Y=	λ		
				X=	ϕ		
				Y=	λ		
COMPUTED BY L.B. Foltz				COMPUTATION CHECKED BY F.R. Gustafson		DATE 11/12/73	
LISTED BY				LISTING CHECKED BY		DATE	
HAND PLOTTING BY				HAND PLOTTING CHECKED BY		DATE	

COMPILATION REPORT

TP-00270

31. DELINEATION

Delineation was by the Wild B-8 stereoplotter.

Photo coverage was adequate. There was no field inspection prior to compilation. The mean high water line and mean low water line were compiled graphically from tide coordinated infrared ratios.

32. CONTROL

See the attached "Photogrammetric Plot Report," dated: Dec. 10, 1973

33. SUPPLEMENTAL DATA

None

34. CONTOURS AND DRAINAGE

Contours are not applicable to the project. Drainage was delineated by the Wild B-8 stereoplotter and by office interpretation of the photographs.

35. SHORELINE AND ALONGSHORE DETAILS

Alongshore details were delineated by the Wild B-8 stereoplotter and by office interpretation of the photographs.

The mean high and mean low water lines were delineated from the tide coordinated photographs.

36. OFFSHORE DETAILS

No statement required.

37. LANDMARKS AND AIDS

Copies of Form 76-40 for 2 landmarks were forwarded to the Rockville, MD office on May 20, 1974.

38. CONTROL FOR FUTURE SURVEYS

None

39. JUNCTIONS

See the attached Form 76-36b, item #5 of the Descriptive Report, concerning junctions.

40. HORIZONTAL AND VERTICAL ACCURACY

No statement required

46. COMPARISON WITH EXISTING MAPS

A comparison has been made with the following U.S. Geological Survey Quadrangle: EDISTO BEACH, SC, dated 1956, scale 1:24,000.

47. COMPARISON WITH NAUTICAL CHARTS

A comparison has been made with the following National Ocean Survey chart: Number 793, 6th edition, dated October 21, 1972, scale 1:40,000.

ITEMS TO BE APPLIED TO NAUTICAL CHARTS IMMEDIATELY

None

ITEMS TO BE CARRIED FORWARD

None

Submitted by:

Albert C. Rauck, Jr.
for L.B. Foltz
Carto. Technician, Nov., 1973

Approved:

Albert C. Rauck, Jr.
Albert C. Rauck, Jr.
Chief, Coastal Mapping Section, AMC

19 August 1975

GEOGRAPHIC NAMES

FINAL NAME SHEET

PH-7101 (Charleston, S. C. to Savannah, Ga.)

TP-00270

Atlantic Ocean

Bay Point

Edisto Beach

Edisto Island

Approved by



Chas. E. Harrington
Staff Geographer-C51x2

NOAA FORM 75-74 (2-74)		U.S. DEPARTMENT OF COMMERCE NOAA NATIONAL OCEAN SURVEY	
PHOTOGRAMMETRIC OFFICE REVIEW			
TP-00270			
1. PROJECTION AND GRIDS A.L.S.	2. TITLE A.L.S.	3. MANUSCRIPT NUMBERS A.L.S.	4. MANUSCRIPT SIZE A.L.S.
CONTROL STATIONS			
5. HORIZONTAL CONTROL STATIONS OF THIRD-ORDER OR HIGHER ACCURACY A.L.S.	6. RECOVERABLE HORIZONTAL STATIONS OF LESS THAN THIRD-ORDER ACCURACY (Topographic stations) NA		7. PHOTO HYDRO STATIONS X X
8. BENCH MARKS NA	9. PLOTTING OF SEXTANT FIXES None	10. PHOTOGRAMMETRIC PLOT REPORT A.L.S.	11. DETAIL POINTS A.L.S.
ALONGSHORE AREAS (Nautical Chart Data)			
12. SHORELINE A.L.S.	13. LOW-WATER LINE A.L.S.	14. ROCKS, SHOALS, ETC. X X	15. BRIDGES X X
16. AIDS TO NAVIGATION X X	17. LANDMARKS A.L.S.	18. OTHER ALONGSHORE PHYSICAL FEATURES X X	19. OTHER ALONGSHORE CULTURAL FEATURES A.L.S.
PHYSICAL FEATURES			
20. WATER FEATURES X X		21. NATURAL GROUND COVER NA	
22. PLANETABLE CONTOURS NA		23. STEREOSCOPIC INSTRUMENT CONTOURS NA	
24. CONTOURS IN GENERAL NA		25. SPOT ELEVATIONS NA	
26. OTHER PHYSICAL FEATURES A.L.S.		27. ROADS A.L.S.	
28. BUILDINGS X X		29. RAILROADS X X	
30. OTHER CULTURAL FEATURES X X		31. BOUNDARY LINES NA	
32. PUBLIC LAND LINES NA		33. GEOGRAPHIC NAMES A.L.S.	
34. JUNCTIONS A.L.S.		35. LEGIBILITY OF THE MANUSCRIPT A.L.S.	
36. DISCREPANCY OVERLAY A.L.S.		37. DESCRIPTIVE REPORT A.L.S.	
38. FIELD INSPECTION PHOTOGRAPHS X X		39. FORMS A.L.S.	
40. REVIEWER G.R. Vanderhaven		SUPERVISOR REVIEW SECTION OR UNIT A.C. Rauck, Jr.	
41. REMARKS (See attached sheet)			
FIELD COMPLETION ADDITIONS AND CORRECTIONS TO THE MANUSCRIPT			
42. Additions and corrections furnished by the field completion survey have been applied to the manuscript. The manuscript is now complete except as noted under item 43.			
COMPILER Field Edit: J.R. Minton 3/25/74		SUPERVISOR A.C. Rauck, Jr.	
Reviewer: G. Vanderhaven 3/25/74			
43. REMARKS Field edit applied from Field Edit ozalid and Photo 71 E 2302R			

FORESHORE CROSS-SECTIONS

CHARLESTON, SOUTH CAROLINA TO SAVANNAH, GEORGIA

JOB PH-7101

Sixteen foreshore cross-sections were taken between Folly Island, South Carolina, and Tybee Island, Georgia, a linear distance of approximately seventy miles. Twelve sections were positioned from triangulation and/or traverse stations and two sections, II and XIII, were located from photo points with sun azimuths. Section IX was located from a triangulation station using a photo point for an azimuth and section VII was run parallel to a relatively long pier.

Vertical control for sections I thru VI, VIII and IX was taken from the tide staff at Edisto Beach, South Carolina. Section VII was based on a temporary tide staff installed at Harbor River Entrance, South Carolina, and a temporary tide staff placed at Skull Creek(North Entrance) provided the control for sections X and XI. The remaining sections were based on the tide staff at Savannah River Entrance, Georgia.

The procedure, in establishing the TBM's used to control the individual sections, was to take a level reading on a recoverable object for use as a TBM, record it as a foresight, and then send the rodman into the water where the rod was used as a combination tide staff/level rod. After observing the water level on the rod for a period sufficient to determine a mean reading, a level reading was taken. The water level reading was subtracted from the level reading and the result entered in the field book as a backsight. Immediately, the instrument was moved, a new water level reading determined and another level reading obtained. Again the two were subtracted and the result entered as a foresight. The rodman was then sent back to the TBM to close the loop. The entries in the field book show this procedure reversed. This was done to avoid confusion as there didn't appear to be any adequate method of showing the actual procedure. The

(2)

One typical section and three atypical sections were plotted to give the compiler an idea of what was done and to show the method of location. These sections, the field book, pricking cards, sun azimuths, color contact photographs and charts showing the individual section locations are included with this report.

Rich E. Kesselring
Richard E. Kesselring
Survey Tech.
May 3, 1971

FIELD EDIT REPORT

TP-00270

EDISTO ISLAND, SOUTH CAROLINA
PH-710151. METHODS

All field work was done in accordance with the AMC Manual, current Photo Instructions and Project Instructions OPR-436-WH-74, "Coasts of South Carolina and Georgia" dated November 16, 1973 addressed to Chief, Atlantic Hydrographic Field Party.

An inspection of all shoreline and alongshore features was made, and all deletions, additions, corrections and verifications are either shown or indexed on the field edit ozalid. All field edit notes are in violet ink.

Lankmarks were located by photogrammetric field methods.

52. ADEQUACY OF COMPILATION

Compilation of shoreline and alongshore features was generally adequate and will be complete when field edit notes are applied.

54. RECOMMENDATIONS

None.

56. GEOGRAPHIC NAMES

No discrepancies in geographic names were found while editing this sheet.

57. LANDMARKS AND AIDS TO NAVIGATION

Two landmarks, Edisto Beach Water Company Tank and a microwave relay tower, are recommended for charting. The water tank is identified on photo 28Mar71E2302. The microwave tower was located from photo points 70-01 and 70-02 as noted on the front and back of photo 28Mar 71E2302. Forms 76-40 have been submitted for each of them.

58. FIELD EDITORS

Field edit was done by Lt. (jg) Richard D. Black and Mr. Michael F. Sutphin of Photo Party 61.

Respectfully Submitted,

Richard D. Black

Richard D. Black
Lt. (jg) NOAA
Chief, Photo Party 61

REVIEW REPORT TP-00270

SHORELINE

October 1975

61. GENERAL STATEMENT:

See Summary which is page six of this Descriptive Report.

A comparison print showing differences noted in paragraphs 62, 63 and 65 is included with the original of this report.

62. COMPARISON WITH REGISTERED TOPOGRAPHIC SURVEYS:

A comparison was made with T-12614, scale 1:20,000, dated April 1966. Significant differences are shown in blue on the comparison print. In the area compared, TP-00270 supersedes T-12614 for nautical chart construction purposes. T-12614 is the latest registered prior survey of the area.

63. COMPARISON WITH MAPS OF OTHER AGENCIES:

A comparison was made with U.S.G.S. Quadrangle EDISTO BEACH, SC, scale 1:24,000, dated 1956. A significant difference is shown in brown on the comparison print.

64. COMPARISON WITH CONTEMPORARY HYDROGRAPHIC SURVEYS:

There was no contemporary hydrographic survey coverage of this sheet.

65. COMPARISON WITH NAUTICAL CHARTS:

The area covered by this map is within the limits of NOAA Chart 11517, 7th edition, scale 1:40,000, dated August 24, 1974. A significant difference on Bay Point is shown in red on the comparison print.

66. ADEQUACY OF RESULTS AND FUTURE SURVEYS:

This map complies with Project Instructions, except as explained in Summary and meets the requirements for Bureau Standards and the National Standards of Map Accuracy.

Reviewed by:

Billy H. Barnes

Billy H. Barnes
Cartographer
October, 1975

Approved for forwarding:

Joseph W. Vonasek

Joseph W. Vonasek
Chief, Photogrammetric Branch, AMC

Approved:

Chief, Photogrammetric Branch

Chief, Coastal Mapping Division

TP-00270

TP-00270²⁰
Scale 1:20,000

523'00"

