

TP-00979

TP-00979

NOAA FORM 76-35 (3-76) U.S. DEPARTMENT OF COMMERCE NATIONAL OCEANIC AND ATMOSPHERIC ADMINISTRATION NATIONAL OCEAN SURVEY	
DESCRIPTIVE REPORT	
Map No. TP-00979	Edition No. 1
Job No. CM-7715	
Map Classification Final Field Edited	
Type of Survey Shoreline	
LOCALITY	
State Florida	
General Locality Tampa Bay	
Locality Snell Isle to Lewis Island	
1977 TO 1978	
REGISTRY IN ARCHIVES	
DATE	

NOAA FORM 76-36A (3-72)		U. S. DEPARTMENT OF COMMERCE NATIONAL OCEANIC AND ATMOSPHERIC ADMIN.		TYPE OF SURVEY		SURVEY TP. 00979	
DESCRIPTIVE REPORT - DATA RECORD				☒ ORIGINAL		MAP EDITION NO. (1)	
				☐ RESURVEY		MAP CLASS Final Field	
☐ REVISED				JOB edited		PH. CM-7715	
PHOTOGRAMMETRIC OFFICE				LAST PRECEDING MAP EDITION			
Rockville, Md.				TYPE OF SURVEY		JOB PH. _____	
OFFICER-IN-CHARGE				☐ ORIGINAL		MAP CLASS _____	
Cmdr. James Collins				☐ RESURVEY		SURVEY DATES:	
				☐ REVISED		19 ____ TO 19 ____	
I. INSTRUCTIONS DATED							
1. OFFICE				2. FIELD			
General Instructions-Office-NOS Cooperative Coastal Boundary Mapping-Job PH-7000 9 December 1975 Office 18 August 1977 Amendment I 3 January 1978 Amendment II 7 March 1978				Field Instructions 27 December 1976 Field Instructions 11 August 1977 Amendment - Field Edit Procedures 30 January 1978			
II. DATUMS							
1. HORIZONTAL: ☒ 1927 NORTH AMERICAN				OTHER (Specify)			
2. VERTICAL: ☒ MEAN HIGH-WATER ☐ MEAN LOW-WATER ☐ MEAN LOWER LOW-WATER ☐ MEAN SEA LEVEL				OTHER (Specify)			
3. MAP PROJECTION				4. GRID(S)			
Lambert Conformal Conic				STATE Florida		ZONE West	
5. SCALE 1:10,000				STATE		ZONE	
III. HISTORY OF OFFICE OPERATIONS							
OPERATIONS				NAME		DATE	
1. AEROTRIANGULATION METHOD: Analytic				BY S. Solbeck		March 1978	
LANDMARKS AND AIDS BY				N/A			
2. CONTROL AND BRIDGE POINTS METHOD: Coradomat				PLOTTED BY J. Taylor		April 1978	
CHECKED BY				N/A			
3. STEREOSCOPIC INSTRUMENT COMPILATION				PLANIMETRY BY			
INSTRUMENT:				CHECKED BY			
SCALE:				CONTOURS BY			
CHECKED BY				N/A			
4. MANUSCRIPT DELINEATION				PLANIMETRY BY A. Bethea		June 1978	
METHOD: Graphic				CHECKED BY J. Battley		July 1978	
SCALE: 1:10,000				CONTOURS BY			
HYDRO SUPPORT DATA BY				N/A			
CHECKED BY							
5. OFFICE INSPECTION PRIOR TO FIELD EDIT				BY J. Battley		July 1978	
6. APPLICATION OF FIELD EDIT DATA				BY P. Dempsey		Oct 1978	
CHECKED BY				J. Battley		Oct 1978	
7. COMPILATION SECTION REVIEW				BY F. Wright		Jan 1979	
8. FINAL REVIEW				BY P. Dempsey		Mar 1984	
9. DATA FORWARDED TO PHOTOGRAMMETRIC BRANCH				BY			
10. DATA EXAMINED IN PHOTOGRAMMETRIC BRANCH				BY P. Dempsey		Mar 1984	
11. MAP REGISTERED - COASTAL SURVEY SECTION				BY E. DAUGHERTY		Nov 1984	

COMPILATION SOURCES

TP-00979

1. COMPILATION PHOTOGRAPHY

CAMERA(S) RC-8-E, RC-10-B		TYPES OF PHOTOGRAPHY LEGEND		TIME REFERENCE	
TIDE STAGE REFERENCE ☐ PREDICTED TIDES ☐ REFERENCE STATION RECORDS ☒ TIDE CONTROLLED PHOTOGRAPHY		(C) COLOR (P) PANCHROMATIC R W INFRARED		ZONE Eastern	☒ STANDARD
				MERIDIAN 75th	☐ DAYLIGHT
NUMBER AND TYPE	DATE	TIME	SCALE	STAGE OF TIDE	
77E(C) 4166-4169	10/13/77	1037	1:30,000	The stage of tide is inapplicable for color photography Refer to 76-36B(1) for tide information	
77B(R) 0253-0255	11/8/77	1149	1:30,000		

REMARKS

The rectified photography is B&W from the color photographs listed above.

2. SOURCE OF MEAN HIGH-WATER LINE:

The source of the MHW line is the tide-coordinated, black and white, infrared photography listed in item 1. Where the MHW line is obscured by vegetation, such as mangrove, the apparent shoreline is delineated.

3. SOURCE OF MEAN LOW-WATER OR MEAN LOWER LOW-WATER LINE:

GCLW photography was not available at time of compilation within accuracy standards. The low-water line was not compiled.

4. CONTEMPORARY HYDROGRAPHIC SURVEYS (List only those surveys that are sources for photogrammetric survey information.)

SURVEY NUMBER	DATE(S)	SURVEY COPY USED	SURVEY NUMBER	DATE(S)	SURVEY COPY USED
Inapplicable					

5. FINAL JUNCTIONS

NORTH TP-00976	EAST TP-00980	SOUTH TP-00982	WEST N/A
-------------------	------------------	-------------------	-------------

REMARKS

Final junctions will be made in the Coastal Mapping Section.

NOAA FORM 76-36B(1)
(7-75)U. S. DEPARTMENT OF COMMERCE
NATIONAL OCEANIC AND ATMOSPHERIC ADMINISTRATION
NATIONAL OCEAN SURVEY

TIDE - COORDINATED PHOTOGRAPHY

TP - 00979

LOCATION AND PHOTOGRAPHY	TIDE STATIONS (In operation at time of photography)	STAGE OF TIDE	MEAN RANGE
77-B-0253-0255R	MHW	- 0.10	
77-B-0255R	Municipal Pier (6520) (St. Petersburg)	- 0.10	
77-B-0253R	Big Bayou (6485)	- 0.10	
77-B-0253R	Little Bayou (6474)	- 0.10	

REMARKS:

HISTORY OF FIELD OPERATIONS

TP-00979

I. ☐ FIELD INSPECTION OPERATION☒ FIELD EDIT OPERATIONUnder ltr. dtd. 1/30/78 fr
Chief, Coastal Mapping

OPERATION	NAME	DATE
1. CHIEF OF FIELD PARTY	R. R. Wagner	August 1978
2. HORIZONTAL CONTROL	RECOVERED BY N/A ESTABLISHED BY N/A PRE-MARKED OR IDENTIFIED BY N/A	
3. VERTICAL CONTROL	RECOVERED BY N/A ESTABLISHED BY N/A PRE-MARKED OR IDENTIFIED BY N/A	
4. LANDMARKS AND AIDS TO NAVIGATION	RECOVERED (Triangulation Stations) BY N/A LOCATED (Field Methods) BY N/A IDENTIFIED BY N/A	
5. GEOGRAPHIC NAMES INVESTIGATION	TYPE OF INVESTIGATION ☐ COMPLETE ☐ SPECIFIC NAMES ONLY ☒ NO INVESTIGATION	
6. PHOTO INSPECTION	CLARIFICATION OF DETAILS BY J. D. Di Mare	Aug 1978
7. BOUNDARIES AND LIMITS	SURVEYED OR IDENTIFIED BY N/A	

II. SOURCE DATA

1. HORIZONTAL CONTROL IDENTIFIED

2. VERTICAL CONTROL IDENTIFIED

PHOTO NUMBER	STATION NAME	PHOTO NUMBER	STATION DESIGNATION

3. PHOTO NUMBERS (Clarification of details)

77E-4166, 4167 & 4168;

4. LANDMARKS AND AIDS TO NAVIGATION IDENTIFIED

PHOTO NUMBER	OBJECT NAME	PHOTO NUMBER	OBJECT NAME

5. GEOGRAPHIC NAMES: ☐ REPORT ☒ NONE6. BOUNDARY AND LIMITS: ☐ REPORT ☒ NONE

7. SUPPLEMENTAL MAPS AND PLANS

8. OTHER FIELD RECORDS (Sketch books, etc. DO NOT list data submitted to the Geodesy Division)

NOAA FORM 76-36D
(3-72)U. S. DEPARTMENT OF COMMERCE
NATIONAL OCEANIC AND ATMOSPHERIC ADMINISTRATION

RECORD OF SURVEY USE

TP-00979

I. MANUSCRIPT COPIES

COMPILATION STAGES			DATE MANUSCRIPT FORWARDED	
DATA COMPILED	DATE	REMARKS	MARINE CHARTS	HYDRO SUPPORT
Class III	7/12/78			
Final	10/20/78			

II. LANDMARKS AND AIDS TO NAVIGATION

1. REPORTS TO MARINE CHART DIVISION, NAUTICAL DATA BRANCH

NUMBER pages	CHART LETTER NUMBER ASSIGNED	DATE FORWARDED	REMARKS
4		6/26/79	Digitized forms (76-40) submitted

2. ☐ REPORT TO MARINE CHART DIVISION, COAST PILOT BRANCH. DATE FORWARDED: _____3. ☐ REPORT TO AERONAUTICAL CHART DIVISION, AERONAUTICAL DATA SECTION. DATE FORWARDED: _____

III. FEDERAL RECORDS CENTER DATA

1. ☒ BRIDGING PHOTOGRAPHS; ☒ DUPLICATE BRIDGING REPORT; ☒ COMPUTER READOUTS.
 2. ☒ CONTROL STATION IDENTIFICATION CARDS; ☐ FORM NOS 567 SUBMITTED BY FIELD PARTIES.
 3. ☒ SOURCE DATA (except for Geographic Names Report) AS LISTED IN SECTION II, NOAA FORM 76-36C.
 ACCOUNT FOR EXCEPTIONS:

4. ☒ DATA TO FEDERAL RECORDS CENTER. DATE FORWARDED: _____


IV. SURVEY EDITIONS (This section shall be completed each time a new map edition is registered)

SECOND EDITION	SURVEY NUMBER TP - _____ (2)	JOB NUMBER PH - _____	TYPE OF SURVEY ☐ REVISED ☐ RESURVEY MAP CLASS ☐ II. ☐ III. ☐ IV. ☐ V. ☐ FINAL
	DATE OF PHOTOGRAPHY	DATE OF FIELD EDIT	
THIRD EDITION	SURVEY NUMBER TP - _____ (3)	JOB NUMBER PH - _____	TYPE OF SURVEY ☐ REVISED ☐ RESURVEY MAP CLASS ☐ II. ☐ III. ☐ IV. ☐ V. ☐ FINAL
	DATE OF PHOTOGRAPHY	DATE OF FIELD EDIT	
FOURTH EDITION	SURVEY NUMBER TP - _____ (4)	JOB NUMBER PH - _____	TYPE OF SURVEY ☐ REVISED ☐ RESURVEY MAP CLASS ☐ II. ☐ III. ☐ IV. ☐ V. ☐ FINAL
	DATE OF PHOTOGRAPHY	DATE OF FIELD EDIT	

NOAA FORM 76-36D

JOB CM-7715
TAMPA BAY, FLORIDA
SHORELINE MAPPING
SCALE 1:40,000 & 1:20,000

REV. 7-20-78



SUMMARY TO ACCOMPANY
DESCRIPTIVE REPORT

Coastal Zone Map TP-00979 is one of fourteen 1:10,000 scale and one 1:20,000 scale shoreline maps in Project CM-7715. These maps are intended for planning purposes for the state of Florida and for the construction and maintenance of NOS Nautical Charts.

The layout for CM-7715 will show the location of the individual maps from Rattlesnake Key to Oldsmar, Florida. A copy of the layout is included in this Descriptive Report.

Field operations consisted of premarking horizontal control and photographing the area, establishing tidal datums and performing the field edit.

Color compilation photography was taken with the RC-8-E camera at 1:30,000 scale in October, 1977 and used in clarifying detail and compiling landmarks and aids to navigation. The shoreline was compiled using 1:30,000 scale infrared MEW photography taken with the RC-10-B & K cameras in November, 1977.

The Aerotriangulation Unit in Rockville, Maryland bridged five strips of 1:60,000 scale black and white photography using analytic aerotriangulation methods.

Compilation was completed in the Coastal Mapping Unit, Rockville, Maryland, using graphic methods.

Field edit was completed in September, 1978. Recovery and location of landmarks, fixed aids to navigation, piling, etc., were omitted from the field edit procedures as per memo dated January 30, 1978, from chief, Coastal Mapping Branch. These items were compiled, to the extent possible, by office photogrammetric methods. The editor was required to only visually verify their existence at the time of edit. Their locations were not field checked. Field edit requirements in the foreshore and adjacent areas remain unchanged.

Application of field edit was performed in the Coastal Mapping Unit, Rockville, Maryland.

Final Review was performed in the Quality Control Unit, Rockville, Maryland, in March, 1984. This map meets the requirements for National Standards of Map Accuracy.

The context of this Descriptive Report contains all pertinent reports and listings of data used to compile this final map.

FIELD REPORT FOR CM-7715 & CM-7717

1. GENERAL

This report covers pre-marking, photo identification of control points, high and low water photographs. The project instructions were changed by Chief, Planning Branch in the range of tide for tidal photographs due to weather conditions.

Due to the size of pre-mark targets and the congestion of the area and targets being destroyed it was necessary to photo identify control points. This part of the field work was delayed due to receiving of the necessary photographs.

There were a number of tide gages in operation at the time of photography that could be used to supplement tidal data.

2. HORIZONTAL CONTROL

The following control stations were pre-marked or identified.

Control Point No. 1 DUNEDIN MUN N TANK 1972, Sub-point marked with array No. 1 with one wing. The data for this station was submitted with CM-7612 target No. 8. This station was not marked again because the grass on the golf course is still dead from when it was paneled a year ago. This panel should be transferred from CM-7612 photos.

Control Point No. 2 BOOTH 1926, Marked direct with array No. 1 and two wings.

Control Point No. 3 CYPRESS 2 1960 1975, Sub-point marked with array No. 1 and no wings. No room for wings.

Control Point No. 4 PETER 1946, Station marked direct with array No. 1 and no wings.

Control Point No. 5 TAMPA PENINSULAR TELEPHONE CO. MOBILE MAST 1955, Station marked direct on old base for tower without wings at request of owner.

Control Point No. 6 COL 1957. No target used. Station is a good point in center of bay in sea wall.

Control Point No. 7 PORT TAMPA, BLACK MUN TANK 1945, Station marked with array No. 1 on remains of standpipe. The tank has been removed. The four tank footings should be used as wings.

Control Point No. 8 GADSDEN 2 1908, Station marked direct with two wings.

Control Point No. 9 Y6 (FGS) 1934, Station marked direct with two wings.

Control Point No. 10 GANDY 1973, Station marked direct with one wing.

Control Point No. 11 BRIGHTWATER B 1973, Sub-point is center of approx. 12X12 foot dock. No target used, see photo 77C7488.

Control Point No. 12 FEDERAL 1973, Station marked direct on top of building. No wings used.

Control Point No. 13 TAMP 1954, Sub-point marked with array No. 1 and one wing.

Control Point No. 14 DESOTO 1973, Sub-point with no target used.

Control Point No. 15 STUMP 1957, Sub-point. Panel destroyed and not replaced. Rockville office stated not needed because other target appears on this line.

Control Point No. 16 SUN CITY POWER CO SILVER WATER TANK 1934, Marked direct in center of four footings with array No. 1 without wings. Tank has been removed.

Control Point No. 17 GILLETTE 1934, Sub-point is the center of three concrete slabs in cemetery. No target used.

Control Point No. 18 MCNIEL 2 1958, Sub-point panel was marked with array No. 1 without wings. This panel was not in place at time of photography. Other sub-points A & B were identified on photo 77C7504.

Control Point No. 19 PALM 3 1924, Sub-point marked with array No. 1 without wings. Wings were not used at request of owner.

Control Point No. 20 MANATEE SILVER MUN WATER TANK 1925 (Cor of 10th St. and 9th Ave), Sub-point marked with array No. 1 and no wings.

Control Point No. 21 CONNER 1954, Station marked direct with array No. 1 without wings. No room for wings.

Control Point No. 22 SCHROEDER 1934, Station marked direct with array No. 1 and two wings.

Control Point No. 23 AMBER TR 27 (USE) 1953, Sub-point marked with array No. 1 and two wings.

Control Point No. 24 WHITFIELD ESTATES TANK 1934, Marked direct with array No. 1 and no wings. Tank is destroyed and target placed in center of tank footings.

Control Point No. 25 SARASOTA, RADIO STATION WSPB MAST 1953, Concrete base identified direct on 77C7516. The mast has been removed and a new mast was built west of old base in the last part of 1970.

Control Point No. 26 NORTHWEST 1878, Two sub-points were identified on photo 77C7518

Control Point No. 27 TT 41 JA 1952, Two sub-points were identified on photo 77C7523

3. PHOTOGRAPHS

Bridging - All bridging photography was flown on October 5, 1977.

Low Water - Flown on October 13 and 14, 1977

High Water - Flown on October 14 and November 8, 1977


4. TIDAL DATA

Leveling for tide station 872 6621, Port Tampa was done by this party and is submitted in one NOAA Form 76-77 for prior and after photography. All other tide stations used were leveled by Photo Party 65 when pages were removed. This data is in Tides Branch, Rockville, Maryland.

The following twelve tidal stations were used:

872-6520 (St Petersburg) in two volumes, 872-5943 (Blackburn Point) and 872-5889 (Venice, Roberts Bay) in one volume, 872-6621 (Port Tampa), 872-6247 (Bradenton), 872-6348 (Two Brothers Island), 872-6243 (Anna Maria), 872-6278 (Redfish Point), 872-6537 (Apollo Beach), 872-6159 (Whitfield Estates), 872-6738 (Safety Harbor) and 972-6639 (Ballast Point.)

Submitted 1/31/78


Robert R. Wagner

Chief, Photo Party 66

PHOTOGRAMMETRIC PLOT REPORT

CM-7715

Tampa Bay, Florida

April 1978

21. Area Covered

The area covered by this report is the immediate shoreline surrounding Tampa Bay, Florida.

Fourteen 1:10,000 scale manuscripts (TP-00970 thru TP-00982 and TP-00984) and one 1:20,000 scale manuscript (TP-00983) are submitted.

22. Method

Five strips of 1:60,000 scale black-and-white photography were bridged by analytic aerotriangulation methods. Control was field identified. Office identified control was used as a check.

Tie points were used to insure adequate junctioning during the strip adjustments. Tie points were also used to ensure adequate junctioning between project CM-7612 and this project. These latter tie points provided the initial control for strip 77-C 7393 to 7401.

Common points were located on the bridging photography and the tide-coordinated infrared being used for ratio purposes. Additional common points were located between the bridging photography and the 1:30,000 scale color photography for compilation purposes. These latter points were located by the compilation section.

The manuscripts will be plotted by the compilation section.

23. Adequacy of Control

The majority of control proved adequate according to National Map Accuracy standards.

The position for Tampa Peninsular Telephone Company Mobile Mast, 1955 (401 100) would not fit into the adjustment by 310 feet in X and 998 feet in Y. The panel was apparently not located correctly by the field party. The correct image was located and measured accurately. The paneled location was measured on two separate strips and used to tie the strips together.

24. Supplemental Data

USGS quads were used to provide vertical control for the strip adjustments. Nautical charts 11413 and 11414 were used to locate aids and landmarks.

25. Photography

The coverage, overlap, and quality of the photography were adequate for the job.


26. Comments on Strip Adjustment

Preliminary strip adjustments of strips 2 and 4 indicate that discrepancies exist that are not normally expected. In strip 2 three points were used to form the second degree adjustment curve, and two control points were "floated" - to be used as check points. One fit within 2 feet and the other was off about 10 feet. These same two points were also "floated" in strip 3, both fit within less than 3 feet.


A similar phenomenon exists on strip 4 where again three points are used for the adjustment and a seemingly good check point is off about 12 feet.


The cause of this "lack of fit" can not be satisfactorily explained, however, the discrepancies in the vicinity of these control points can be reduced by using them in the adjustment. By doing this, they fit to within 6 feet.


Submitted by,


Steve Solbeck

Approved and forwarded:


Acting Chief, Aerotriangulation Section





TAMPA BAY, FLORIDA CM-7715

Accruacy of Control

		X	Y
STRIP #1	258830	- .075	+ .558
	352820	+ .407	- .915
	396100	+ .728	+ .686
	398101	+ .318	+ .045
	400100	+ .064	- .938
	401141	+ .020	+ .559
STRIP #2	487100	-1.574	+ 2.163
	488101	- .563	- 5.231
	489101	-1.510	+ 2.273
	490100	+4.496	+ .554
	203801	- .851	+ .243
	262830	+ .222	+ 1.876
STRIP #3	423101	+1.262	+ 1.806
	425101	-1.726	- 2.149
	427100	-1.276	- 1.487
	488101	+1.998	- .753
	487100	+2.260	+ 1.868
	489101	+2.764	- 2.448
	478100	-3.540	+ 2.008
	398101	+3.021	- 2.046
STRIP #4	398101	-1.366	- 3.579
	400100	+5.121	- 1.143
	478100	-3.185	+ 3.309
	487100	-2.260	+ 1.533
	480100	+1.085	+ .731
	478801	+ .605	- .851
STRIP #6	528101	-4.052	+ 1.220
	528102	-4.149	- .277
	530101	-1.116	- 2.404
	532100	-1.592	+ 4.189
	480100	+4.226	- 2.684
	401141	+4.864	- 2.402
	401100	- .248	+ .134
	401111	-1.335	+ 1.275

DESCRIPTIVE REPORT CONTROL RECORD

MAP NO.	STATION NAME	JOB NO.	SOURCE OF INFORMATION (Index)	AEROTRI- ANGULATION POINT NUMBER	GEODETTIC DATUM		ORIGINATING ACTIVITY		
					STATE	ZONE	COORDINATES IN FEET	GEOGRAPHIC POSITION	
					FLORIDA		φ LATITUDE	λ LONGITUDE	REMARKS
					West				
TP-00979		CM-7715				N A 1927			Rockville, Md.
St. Petersburg Clark Sunset Golf Course, Red W.T., 1934	PC pg 12			188			x= 299,285.11 y= 1,259,357.58	φ λ	
St. Petersburg Vinoy Park Hotel, Cupola, 1936	Geodeyic listing p 7			427143			x= 296,083.269 y= 1,252,412.541	φ 27° 46' 40.278" λ 82° 37' 50.232"	
St. Petersburg First Metho- dist Ch Tower, 1973	Geod. List. pg 6			169			x= 293,850.414 y= 1,250,808.127	φ 27° 46' 24.277" λ 82° 38' 14.992"	
St. Petersburg, St. Peters Episcopal Ch, Spire, 1973	Geod. List. pg 7			170			x= 293,400.902 y= 1,250,674.049	φ 27° 46' 22.926" λ 82° 38' 19.993"	
St. Petersburg, Rutland Bldg Cupola, 1973	"			427144			x= 293,399.083 y= 1,249,963.573	φ 27° 46' 15.891" λ 82° 38' 19.972"	
Federal, 1973	PC pg 3			427100			x= 294,523.184 y= 1,249,460.933	φ λ	
St. Petersburg, St. Marys Catholic Ch, Cupola, 1973	Geod. List. pg 7			427142			x= 293,345.438 y= 1,247,774.942	φ 27° 45' 54.216" λ 82° 38' 20.443"	
St. Petersburg, Municipal 13th Ave Tank, 1934	Zone 3 pg12 vol I p 207			427141			x= 292,858.396 y= 1,254,934.958	φ 27° 47' 05.091" λ 82° 38' 26.280"	
Tampa Bay Cut K Channel Range Rear Light, 1957	Vol II Pg 87			300			x= 311,772.11 y= 1,259,999.39	φ 27° 47' 56.172" λ 82° 34' 55.974"	
							x=	φ	
							y=	λ	
COMPUTED BY				DATE		COMPUTATION CHECKED BY			DATE
LISTED BY	A. Betha			DATE	June 1978	LISTING CHECKED BY	J. Battley		DATE
HAND PLOTTING BY				DATE		HAND PLOTTING CHECKED BY			DATE

DESCRIPTIVE REPORT CONTROL RECORD

MAP NO.	JOB NO.	STATION NAME	SOURCE OF INFORMATION (Index)	AEROTRI- ANGULATION POINT NUMBER	GEODETTIC DATUM		GEOGRAPHIC POSITION		REMARKS
					STATE	ZONE	ϕ LATITUDE	λ LONGITUDE	
TP-00979	CM-7715	Tampa Bay Cut G Channel Range Rear Light, 1957	Vol II Pg 88	427150	N	A	306,253.41 1,258,384.88	27° 47' 39.922" 82° 35' 57.336"	
							X=	ϕ	
							Y=	λ	
							X=	ϕ	
							Y=	λ	
							X=	ϕ	
							Y=	λ	
							X=	ϕ	
							Y=	λ	
							X=	ϕ	
							Y=	λ	
							X=	ϕ	
							Y=	λ	
							X=	ϕ	
							Y=	λ	
							X=	ϕ	
							Y=	λ	
							X=	ϕ	
							Y=	λ	
							X=	ϕ	
							Y=	λ	
COMPUTED BY							COMPUTATION CHECKED BY		DATE
LISTED BY							LISTING CHECKED BY		DATE
		A. Bethea					J. Battley		JUNE 1978
HAND PLOTTING BY							HAND PLOTTING CHECKED BY		DATE

Compilation Report

TP-00979

June 1978

31. Delineation

All features were delineated by graphic methods utilizing black and white, rectified prints of the 1:30,000 color photography. The MHW line and apparent shoreline was delineated from ratio, tide-coordinated, infrared photographs which were controlled by common detail compiled from the rectified photographs.

32. Horizontal Control

Horizontal control was adequate. (See Photogrammetric Plot Report)

33. Supplemental Data

Field sketches, indicating the location of applicable tide stations, were supplied by the Tides and Water Levels Section.

34. Contours and Drainage

Contours are not applicable. Drainage was compiled from office interpretation of the ratio, tide-coordinated, black and white, infrared photography.

35. Shoreline and Alongshore Detail

Office interpretation of the tide-coordinated, black and white, infrared photography was adequate.

36. Offshore Details

No unusual problems were encountered.

37. Landmarks and Aids

Refer to Form 76-40.

38. Control for Future Surveys

None

39. Junctions

Refer to Form 76-36B.

40. Horizontal and Vertical Accuracy

This map complies with the accuracy requirements for the Florida Coastal Zone Mapping Program as outlined by project instructions PH-7000.

41. thru 45. Inapplicable

46. Comparison with Existing Maps

Comparison was made with the following USGS Quadrangle Maps:

Pass A Grille Beach, Florida 1969
Port Tampa, Florida 1969
St. Petersburg, Florida 1969

47. Comparison with Nautical Charts

Comparison was made with the following Nautical Charts:

11413, April 16, 1977, 1:40,000
11414, April 9, 1977, 1:40,000

Items to be applied to Nautical Charts immediately: None

Items to be carried forward: None

Submitted by,

Alfred Bethea
Alfred Bethea

Approved and Forwarded:

Jeter P. Battley, Jr.
Jeter P. Battley, Jr.
Chief, Coastal Mapping Section

FIELD EDIT REPORT TP-00979, JOB CM-771551. METHODS

Field edit was performed under instructions dated 1/30/78 from Chief, Coastal Mapping Division, Rockville, Maryland.

The shoreline was inspected from a small boat while cruising just off shore and by truck.

Field edit notes will be found on the photographs and discrepancy print.

52. ADEQUACY OF COMPILATION

Adequate after application of field edit.

53. MAP ACCURACY

No test required.

54. RECOMMENDATIONS

Two landmarks are recommended for deletion. Form 76-40 is submitted.

55. EXAMINATION OF PROOF COPY

Not required.

Submitted: 8/31/78

Joseph D. Di Mare
Joseph D. Di Mare
Surveying Technician

REVIEW REPORT
TP-00979
March 1984

61. General Statement

Refer to the summary bound with this Descriptive Report.

62. Comparison With Registered Topographic Surveys - None

63. Comparison With Maps of Other Agencies

Refer to the Compilation Report, paragraph 46, bound with this Descriptive Report.

64. Comparison With Contemporary Hydrographic Surveys - None


65. Comparison With Nautical Charts

Refer to the Compilation Report, paragraph 47, bound with this Descriptive Report.


66. Adequacy of Results and Future Surveys


This map complies with the Project Instructions and meets the requirements for National Standards of Map Accuracy.

Submitted by,


Patrick J. Dempsey
Cartographer

Approved and Forwarded,


George M. Ball
Chief, Photogrammetric Section


Ronald K. Brewer
Chief, Photogrammetry Branch

February 16, 1979

GEOGRAPHIC NAMES

FINAL NAME SHEET

CM-7715 (Tampa Bay, Florida)

TP-00979

. Bahama Beach (locality)	Mirror Lake
Bayboro Harbor	North Yacht Basin
Bay Point	Round Lake
Big Bayou	Salt Creek
Booker Creek	Snell Isle
Central Yacht Basin	Snell Isle Harbor
Coffeepot Bayou	South Yacht Basin
Crescent Lake	ST. Petersburg
Lake Maggiore	Tampa Bay
Lewis Island	Whitted Airport
Little Bayou	

Approved by:


Charles E. Harrington
Chief Geographer - C3x5

DISSEMINATION OF PROJECT MATERIAL
CM-7715

National Archives/Federal Records Center

Red Jacket:

Field Notebooks - NOAA Forms 77-53
NOAA Form 76-77
Bridging photographs
Tidal bench mark descriptions
Sketches and computations
Field edit discrepancy print
Field photographs
CSI cards

Bureau Archives

Registered copy of each map
Descriptive Report of each map

Reproduction Division

8x Reduction negative of each map

Office of Staff Geographer

Geographic Names Standard

PHOTOGRAMMETRIC BRANCH
COASTAL MAPPING DIVISION

NATIONAL OCEAN SURVEY NOAA
DEPARTMENT OF COMMERCE USA

DATA TAB
VERSION
782707

LISTING

**	SVY	TP00979	**
**	JOB	CM7715	**
**	PRJ	833205	**
**	DTM	NA1927	**

* RPT UNIT CMD, ROCKVILLE, MD. *
* STATE FLORIDA *
* LOCALITY TAMPA BAY *
* DATE 08/21/78 *

PAGE 1 OF 4

INATING ACTIVITY COMPILATION

OBJECTS INSPECTED FROM SEAWARD
* * * POSITIONS DETERMINED
* * * AND/OR VERIFIED BY
* * * FIELD AND OFFICE
* * * ACTIVITIES

JOSEPH DI MARE
JOSEPH DI MARE
JETER P. BATTLE
ALFRED BETHEA
JAMES H. TAYLOR

* * * * *

KEY FOR ENTRIES UNDER METHOD AND DATE OF LOCATION

OFFICE

* FIELD(CONT,D)

1. OFFICE IDENTIFIED AND LOCATED OBJECTS.
THE NUMBER AND DATE (INCLUDING MONTH, DAY
AND YEAR) OF THE PHOTOGRAPH USED TO
IDENTIFY AND LOCATE THE OBJECT ARE SHOWN.
EXAMPLE 75E(C)6042

PHOTOGRAMMETRIC FIELD POSITIONS** SHOW
THE METHOD OF LOCATION OR VERIFICATION,
DATE OF FIELD WORK AND NUMBER OF PHOTO-
GRAPH USED TO LOCATE AND IDENTIFY THE
OBJECT.
EXAMPLE P-8-V

FIELD

1. NEW POSITION DETERMINED OR VERIFIED

KEY TO SYMBOLS

F-FIELD
L-LOCATED
P-PHOTOGRAMMETRIC
VIS-VISUALLY

V-VERIFIED
1-TRIANGULATION
2-TRAVERSE
3-INTERSECTION
4-RESECTION
5-FIELD IDENTIFIED
6-THEODOLITE
7-PLANETABLE
8-SEXTANT

A. FIELD POSITIONS* SHOW THE METHOD OF LOCATION AND DATE OF FIELD WORK.

2. TRIANGULATION STATION RECOVERED

WHEN A LANDMARK OR AID WHICH IS ALSO A TRI-
ANGULATION STATION IS RECOVERED, A TRIANG.
REC. WITH DATE OF RECOVERY IS SHOWN.
EXAMPLE TRIANG. REC.

3. POSITION VERIFIED VISUALLY ON PHOTOGRAPH SHOWN BY V-VIS AND DATE.

*FIELD POSITIONS ARE DETERMINED BY FIELD OBSERVATIONS BASED ENTIRELY UPON GROUND SURVEY METHODS

***PHOTOGRAMMETRIC FIELD POSITIONS ARE
DEPENDENT ENTIRELY,OR IN PART,UPON CONTROL
ESTABLISHED BY PHOTOGRAMMETRIC METHODS.

NOTE: WHERE THE NAME OF AN AID INCLUDES THE IMMEDIATE GEOGRAPHIC HEADING UNDER WHICH IT IS LISTED, A DASH (-) IS USED TO INDICATE THE GEOGRAPHIC HEADING WHICH IS PART OF THE OFFICIAL NAME.

PHOTOGRAMMETRIC BRANCH
COASTAL MAPPING DIVISION

NATIONAL OCEAN SURVEY NOAA
DEPARTMENT OF COMMERCE USA

* SVY TP00979 * RPT UNIT CMD, ROCKVILLE, MD. * PAGE 2 OF 4 *										
* JOB CM7715 * NONFLOATING AIDS FOR CHARTS * STATE FLORIDA * ORIGINATING ACTIVITY *										
* PRJ 833205 * TO BE CHARTED * LOCALITY TAMPA BAY * COMPILATION *										
* DTM NA1927 * DATE 08/21/78 *										
* THE FOLLOWING OBJECTS HAVE NOT BEEN INSPECTED FROM SEAWARD TO DETERMINE THEIR VALUE AS LANDMARKS *										
* DESCRIPTION * POSITION CMD * METHOD AND DATE * CHARTS										
* CHARTING * RECORD REASON FOR DELETION * LATITUDE DM ALTEK * OF LOCATION * FIELD * AFFECTED *										
* NAME * PUT TRIANGULATION NAMES IN () * LONGITUDE DP DGTZD * OFFICE * FIELD * AFFECTED *										
* ONLY THOSE NONFLOATING AIDS AND LANDMARKS TO NAVIGATION * *										
* THAT WERE VISIBLE ON THE PHOTOGRAPHY AND LOCATED DURING * *										
* BRIDGING OR COMPILATION ARE SHOWN ON THIS MAP. * *										
* TAMPA BAY * *										
* TAMPA BAY CUT G CHANNEL * *										
* -RGE R * (TAMPA BAY, CUT G CHANNEL, * 27 47 39.97 1230.3 NOT *TRIANG * 11412										
* LIGHT * RANGE REAR LIGHT, 1957) * 82 35 57.33 1569.4 DGTZD* * 11413										
* TAMPA BAY * *										
* TAMPA BAY CUT K CHANNEL * *										
* -RGE R * (TAMPA BAY, CUT K CHANNEL, * 27 47 56.17 1729.0 NOT *TRIANG * 11412										
* LIGHT * RANGE REAR LIGHT, 1957) * 82 34 55.97 1532.1 DGTZD* * 11413										
* TAMPA BAY * *										
* ST. PETERSBURG HARBOR * *										
* -LIGHT * ST. PETERSBURG YACHT BASIN * 27 46 18.05 555.6 * 77C7426 * 11413										
* WEST MOLE LIGHT * 82 37 38.82 1062.9 * 10/05/77 * *										
* -LIGHT * ST. PETERSBURG YACHT BASIN * 27 46 17.18 528.8 * 77C7426 * *										
* EAST MOLE LIGHT * 82 37 34.21 936.7 * 10/05/77 * 11413										
* * *										
* * *										

PHOTOGRAMMETRIC BRANCH
COASTAL MAPPING DIVISION

NOAA
USA

DATA TAB
VERSION
782707

LISTING

**	SVY	TP00979	**
**	JOB	CM7715	**
**	PRJ	833205	**
**	DTM	NA1927	**

LANDMARKS FOR CHARTS
TO BE DELETED

* RPT UNIT
* STATE
* LOCALITY
* DATE

COMPILATION

THE FOLLOWING OBJECTS HAVE BEEN INSPECTED FROM SEAWARD TO DETERMINE THEIR VALUE AS LANDMARKS

[illegible]

* * *	* (ST, PETERSBURG, ST. PETERS	* 27	46	22.92	705.5	NOT *TRIANG	* V-VIS	* *
* *	SPIRE * EPISCOPAL CHURCH SPIRE, 1973)	* 82	38	19.99	547.3	OGTZO*	* 08/23/78	* 11413 *

* *	* (ST. PETERSBURG, RUTLAND BLDG	* 27 46 15.89	489.1	NOT *TRIANG	*V-VIS	*
* *	* SPIRE * CUPOLA, 1973)	* 82 38 19.97	546.8	DGTZD*	* 08/23/78	* 11413 *

[illegible][illegible][illegible][illegible][illegible]

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47
48
49
50
51
52
53
54
55
56
57
58
59
60
61
62
63
64
65
66
67
68
69
70
71
72
73
74
75
76
77
78
79
80
81
82
83
84
85
86
87
88
89
90
91
92
93
94
95
96
97
98
99
100
101
102
103
104
105
106
107
108
109
110
111
112
113
114
115
116
117
118
119
120
121
122
123
124
125
126
127
128
129
130
131
132
133
134
135
136
137
138
139
140
141
142
143
144
145
146
147
148
149
150
151
152
153
154
155
156
157
158
159
160
161
162
163
164
165
166
167
168
169
170
171
172
173
174
175
176
177
178
179
180
181
182
183
184
185
186
187
188
189
190
191
192
193
194
195
196
197
198
199
200
201
202
203
204
205
206
207
208
209
210
211
212
213
214
215
216
217
218
219
220
221
222
223
224
225
226
227
228
229
230
231
232
233
234
235
236
237
238
239
240
241
242
243
244
245
246
247
248
249
250
251
252
253
254
255
256
257
258
259
260
261
262
263
264
265
266
267
268
269
270
271
272
273
274
275
276
277
278
279
280
281
282
283
284
285
286
287
288
289
290
291
292
293
294
295
296
297
298
299
300
301
302
303
304
305
306
307
308
309
310
311
312
313
314
315
316
317
318
319
320
321
322
323
324
325
326
327
328
329
330
331
332
333
334
335
336
337
338
339
340
341
342
343
344
345
346
347
348
349
350
351
352
353
354
355
356
357
358
359
360
361
362
363
364
365
366
367
368
369
370
371
372
373
374
375
376
377
378
379
380
381
382
383
384
385
386
387
388
389
390
391
392
393
394
395
396
397
398
399
400
401
402
403
404
405
406
407
408
409
410
411
412
413
414
415
416
417
418
419
420
421
422
423
424
425
426
427
428
429
430
431
432
433
434
435
436
437
438
439
440
441
442
443
444
445
446
447
448
449
450
451
452
453
454
455
456
457
458
459
460
461
462
463
464
465
466
467
468
469
470
471
472
473
474
475
476
477
478
479
480
481
482
483
484
485
486
487
488
489
490
491
492
493
494
495
496
497
498
499
500
501
502
503
504
505
506
507
508
509
510
511
512
513
514
515
516
517
518
519
520
521
522
523
524
525
526
527
528
529
530
531
532
533
534
535
536
537
538
539
540
541
542
543
544
545
546
547
548
549
550
551
552
553
554
555
556
557
558
559
560
561
562
563
564
565
566
567
568
569
570
571
572
573
574
575
576
577
578
579
580
581
582
583
584
585
586
587
588
589
590
591
592
593
594
595
596
597
598
599
600
601
602
603
604
605
606
607
608
609
610
611
612
613
614
615
616
617
618
619
620
621
622
623
624
625
626
627
628
629
630
631
632
633
634
635
636
637
638
639
640
641
642
643
644
645
646
647
648
649
650
651
652
653
654
655
656
657
658
659
660
661
662
663
664
665
666
667
668
669
670
671
672
673
674
675
676
677
678
679
680
681
682
683
684
685
686
687
688
689
690
691
692
693
694
695
696
697
698
699
700
701
702
703
704
705
706
707
708
709
710
711
712
713
714
715
716
717
718
719
720
721
722
723
724
725
726
727
728
729
730
731
732
733
734
735
736
737
738
739
740
741
742
743
744
745
746
747
748
749
750
751
752
753
754
755
756
757
758
759
760
761
762
763
764
765
766
767
768
769
770
771
772
773
774
775
776
777
778
779
780
781
782
783
784
785
786
787
788
789
790
791
792
793
794
795
796
797
798
799
800
801
802
803
804
805
806
807
808
809
810
811
812
813
814
815
816
817
818
819
820
821
822
823
824
825
826
827
828
829
830
831
832
833
834
835
836
837
838
839
840
